

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 119 — 20,453
County Number

Operator
CALVIN EXPLORATION, INC.

Address
1125 17th St., Suite 2000, Denver, Colorado 80202

Well No. 1-10 Lease Name Wilson

Footage Location
660' FNL 2640' FEL
feet from (N) (S) line feet from (E) (W) line

Principal Contractor SEARCH DRILLING COMPANY Geologist PAUL M. GERLACH

Spud Date 01-06-81 Date Completed 01-21-81 Total Depth 5900' P.B.T.D. ---


Directional Deviation 1° @ 5052' Oil and/or Gas Purchaser P&A

S 10 T. T34S R. 29W W

Loc. N2 N2

County MEADE

640 Acres
N



Locate well correctly
2208'

Elev.: Gr. 2208'

DF 2216' KB 2218'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Conductor	30"	20"		35'	Redimix	4 yds	
Surface Casing	12-1/4"	8-5/8"	24#	1155'	35/65 Poz	525 sx	6% Tot Gel, 2% CaCl
						150 sx	1/4# D29/sk
							Class H, 3% CaCl,
							1/4# D29/sk

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be trans-
mitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation
Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note
Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
CALVIN EXPLORATION, INC.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.
1-10

Lease Name
WILSON

DRY HOLE

10 T34S-R29W E
T R W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

FORMATION

Red Bed
Red Bed and Lime
Lime and Shale
RTD

0
1660
1963
5900

1600
1963
5900

LOG TOPS:

Heebner 4377'
Lansing 4552'
Marmaton 5226'
Cherokee 5382'
Morrow 5688'
Chester 5719'

DST #1, interval 5730' - 5896'
OP 20", SI 60", OP 60", SI 180". Wk blo on
IF, dead on FF. Rec 10' DM w no sho.
IHP 2924#
IFP 29# & 29#
ISIP 352#
FFP 58# & 88#
FSIP 789#
FHP 2751#
Sampler pressure 10#, contents 2240cc DM.

TD 5900'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

GARY C. WILKINS, VICE PRESIDENT
EXPLORATION-PRODUCTION

Title

FEBRUARY 4, 1981

Date