

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

DAVID-WILSON #1-10
 NE NE NE Sec. 10-34S-26W
 Meade County, Kansas

Commenced: 8-20-84

Completed: 9-4-84

Operator: Kaiser-Francis Oil Company

Depth		Formation	Remarks
From	To		
0	37	Cased Hole	37' of 20" csg.
37	520	Sand-Redbed	
520	1770	Redbed	Ran 20 jts. of 24# 8 5/8" csg.
1770	2225	Redbed-Sand	LD @ 852' w/250 sks Howcolite
2225	6200	Lime-Shale	1/4# Floseal 2% CC 200 sks Class H -- 3% CC
6200	TD		PD @ 3:30 P.M. 8-22-84
			Ran 156 jts. of 15 1/2# 5 1/2" csg. LD @ 6202' First Stage (75 sks Fixset 12 1/2# Gilsonite)
			PD @ 9:30 P.M. 9-3-84
			DV Tool @ 5010' w/55 sks Fixset 12 1/2# Gilsonite
			PD @ 2:00 A.M. 9-4-84

State of Kansas]
 County of Sedgwick]

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.