


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company GRAHAM-MICHAELIS DRILLING CO.
Farm Easterday **No.** 1

SEC. 14 **T.** 34 **R.** 26W
 NE NE SW SE
 60' S & 150' W of C SE/4

County Meade **KANSAS**



Total Depth. 5860'

Comm. 4-25-56

Comp. 5-19-56

Shot or Treated.

Contractor. Graham-Michaelis Drilling Co.

Issued. 8-11-56

CASING:

8 5/8" @ 1181' w/250 sax cem & 450 sax Pozmix
 5 1/2" @ 5857' w/300 sax Com. Cem.

Elevation. ?

Production. 7,000,000 CFGPD

Figures indicate Bottom of Formations.

red bed	1114
red bed & Anhydrite	1620
shale & Anhydrite	1888
Green & Red	
sahel w/Gyp	2125
Anhydrite & shale	2590
lime	2702
lime & shale	2802
lime	2871
lime & shale	4260
shale	4376
shale & lime	4420
shale & lime streaks	4540
lime & shale	4620
lime	4874
lime & shale streaks	4910
shale	4920
lime	5252
lime w/shale	5290
lime	5704
lime & shale	5744
lime, sand & shale	5780
lime	5860 RTD

Total Depth

TOPS:

Heebner	4382
Kansas City	4575
Marmaton	5253
Cherokee	5432
Morrison Shale	5729
Morrison Sand	5750
Chester	5831