

TYPE

State Geological Survey

SIDE ONE

WICHITA, BRANCH

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # Application being prepared EXPIRATION DATE

OPERATOR Getty Oil Company API NO. 15-119-20,565

ADDRESS 2705 Vine, Unit #4 COUNTY Meade

Hays, Kansas 67601 FIELD McKinney

** CONTACT PERSON Frank L. Renard PHONE 913-628-1039 PROD. FORMATION Morrow & Mississippian Chester

PURCHASER Kansas Power & Light Company LEASE C. E. Wooldridge

ADDRESS Box 889, 4th Floor WELL NO. 2

Topeka, Kansas 66601 WELL LOCATION Sec. 20-T34S-R26W

DRILLING Murfin Drilling Company 1369 Ft. from North Line and

CONTRACTOR CONTRACTOR 1497 Ft. from West Line of

ADDRESS 617 Union Center Building the NW/4(Qtr.) SEC 20 TWP 34SRGE 26W. Wichita, Kansas 67202

PLUGGING CONTRACTOR WELL PLAT (Office Use Only)

ADDRESS KCC KGS SWD/REP PLG.

TOTAL DEPTH 6150' PBD 6079'

SPUD DATE 4-15-82 DATE COMPLETED 7-8-82

ELEV: GR 2340' DF 2350' KB 2352'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE C-16,693

Amount of surface pipe set and cemented 1331' DV Tool Used? No

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Frank Renard, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Frank Renard

OPERATOR Getty Oil Company LEASE C. F. Wooldridge SEC. 20 TWP. 34S RGE. 26W

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			SHOW GEOLOGICAL MARKERS LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Loose Sand	0	77		
Red Beds	77	1313		
Anhydrite	1313	1331		
Lime & Shale	1331	1705		
Shale	1705	2550		
Lime & Shale	2550	5425		
Lime & Shale	5425	5617	Marmaton	5425-5617
Lime & Shale	5617	5907	Cherokee	5617-5907
Lime & Shale	5907	5941	Morrow	5907-5941
Sand & Shale	5941	5962	Morrow Sand	5941-5962
Lime & Shale	5962	6150	Chester	5962-6150

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
3200 gal. 7-1/2% De-mud acid	6020-58' OA
7500 gal. 28% HCl & 11,250 gal. 7-1/2% retarded HCl	6020-58' OA
2300 gal. 7-1/2% De-mud acid	5949-54' & 5964-88' OA
Acid fraced w/ 24,000# 20-40 sand in 30,000 gal. Titan XL-3 gel.	5949-54' & 5964-70' 5976-80'
Date of first production	Producing method (flowing, pumping, gas lift, etc.)
Shut in for P.L. Connection	Flowing
	Gravity .60
RATE OF PRODUCTION PER 24 HOURS	OH
	Gas 1057 MCF
	Water XXX 60BPD bbls.
	Gas-oil ratio FTP 75# CFPB
Disposition of gas (vented, used on lease or sold)	Perforations 6020-35', 6041-88' 5949-54', 5976-88' & 5964-70'
Will be sold - Waiting on P.L. Connection	

Ran Schlumberger Dual Induction Log 6144-1327', Compensated Neutron-Formation Density Log 6134-4150', Computer Processed Log 6134-4150' and Cement Bond Log 4250-6076'.

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or ~~(X)~~

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Conductor	26"	16"	65	87'	Redi-Mix	9 yds.	
Surface	12-1/4"	8-5/8"	24	1331'	Lite Class "H"	550 150	2% CaCl2 3% CaCl2
Production	7-7/8"	4-1/2"	10.5 9.5	6144'	Class "H"	355	50-50 Pozmix w/ 10% Salt & 3/4% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	3-1/8" Welex	6020-35' & 6041-58'
TUBING RECORD				SSB II Gun	
Size	Setting depth	Packer set at			
2-3/8" OD	6069'		1	"	5949-54', 5976-88' 5964-70'