

Company- SKELLY OIL CO.

Farm- Dora Taylor


No. 1

SEC. 22 T. 34 R. 26W

1320' ^{C E/2} fr EL 2640' fr SL

County Meade

KANSAS



Total Depth. 6074' PB 5994'

Comm. 8-25-56 Comp. 9-25-56

Shot or Treated.

Contractor. Claude Wentworth Drlg. Co.

Issued. 2-16-57

Elevation. 2312' DF

Production. 1,610,000 CFGPD

CASING:

8 5/8" 890' w/450 sx cem.
 5 1/2" 6073' w/250 sx cem.

Figures Indicate Bottom of Formations.

surface soil-lime 210
 lime-sand 455
 shale-shells 590
 shale 891
 shale-shells 1085
 red bed-salt-lime 1320
 shale-shells 2285
 lime 2310
 lime-shale 2555
 lime 2665
 lime-shale 2835
 shale-shells 2925
 lime-shale 3475
 shale-shells 3530
 lime-shale 3900
 lime 3950
 lime-shale 4790
 shale-shells 4865
 lime-shale 5013
 lime 5065
 lime-shale 5117
 lime 5271
 lime-shale 5288
 lime 5331
 lime-shale 5412
 lime 5442
 lime-shale 5507
 lime 5550
 lime-shale 5723
 lime 5762
 lime-shale 5822
 lime 5838
 lime-shale 5915
 lime-shale 6000
 lime 6014
 lime-shale 6062
 lime 6074

Total Depth PB 5994'

DST # 2- Packer set @ 5950',
 used 64' anchor, open 1 hr.,
 weak blow for 1 hr., rec. 90'
 of slightly wtry. mud, IFP-75#,
 FFP-125#, BHP-825# in 20 min.

DST # 3 - packer set @ 6010',
 used 64' anchor, open 1 hr.,
 light blow for 50 min., rec.
 20' of drilling mud, IFP-40#,
 FFP-40#, BHP-540# in 20 min.

Acid Treatment:

Between 5940-5951' w/500 gals. 10-1-56

Petro-Frac Treatment #1-between
 5940-51' & 5954-58' w/1000 gals.

TOPS:

Heebner shale 4544
 Lansing lime 4710
 Marmaton lime 5404
 Cherokee lime 5614
 Morrow shale 5896
 Morrow sand 5933
 Chester lime 5984

Cored fr 5915-5954' Rec. 36'

DST # 1- Packer set @ 5896',
 used 58' anchor, open 1 hr.,
 weak blow for 30 min. then
 quit, rec. 20' drilling mud.
 IFP-0#, FFP-150#, BHP-230#
 in 20 min.