

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- **TENNESSEE GAS TRANSMISSION CO.**
 Farm- **Davidson Unit No. 1**

SEC. **24** T. **34** R. **26W**
 CW/2

Total Depth. **5937**
 Comm. **4-11-57** Comp. **6-24-57**
 Shot or Treated.
 Contractor. **Capitt Drilling, Inc.**
 Issued. **8-17-57**

County **Meade**

KANSAS



CASING:
8 5/8" 1166' cem w/525 sx.
5 1/2" 5934' cem w/200 sx.

Elevation. **2180 RB**

Open Flow.

Production. **1,300,000 gas**

Figures indicate Bottom of Formations

DST #2 5815-5935 Op. 1 1/4 hrs. - SI 30" Rec. 1080'
mud. BHP 2280#, FP 380-870#

red bed 40
red bed, shells 440
salt 650
red bed, shells 930
lime, shale 1161
anhydrite 1167
sand, salt 1225
shale, shells 2045
shale 2165
lime, shale 2255
lime, shale strks 2340
lime, shale Brkn 2440
lime 2513
shale, lime 3015
shale, chalk strks 3124
lime chalky, shale 3220
lime 3290
lime, chalk strks 3498
lime 3575
lime, chalk strks 3682
lime, shale w/chalk streaks 3773
lime 3865
shale 4017
shale, lime 4150
lime 4240
shale, lime strks 4360
shale, lime 4440
lime 4461
lime, shale 4590
lime 4808
lime, shale, chalk streaks 4894
lime 5220
lime, shale 5274
lime 5639
lime, shale 5711
shale 5768
sand 5770
Core # 1 5810
Core # 2 5821
chert, lime 5838
lime RTD 5935
lime 5937
Total Depth

Perf. 48# 5872-84 N S - 2000 Acid
LWP 5844
Perf. 48 # 4872-92 1/2 N S - 200 Acid
LWP 5844
Perf. 6 # 5797-99, 5803-07, 5809-11,
500 Acid-fraced.

Tops:

Lansing-Kansas City 4510
Marmaton 5208
Cherokee 5466
Atoka 5620
Morrow 5764
Morrow sand 5802
Chester (Miss.) 5811

DST #1 5750-5810, 2 hrs.
gas to surf. 7", 311,000
CFGPD - 180' GCM- 30"
BHP 1880#, FP 115#-150#.

Open Flow.