

ROTARY DRILLING LOG

OPERATOR: J. M. Huber Corporation
 PAINTER "B" #1
 Location: C SE/4 Sec. 18-34S-26W,
 Meade County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
 COMM: 1/27/59
 COMP: 2/22/59

Formations:

Remarks: Set 1442.50' of 8-5/8" surface casing cemented with 750 sacks Pozmix, 2% C.C.

Soil	40'
Sand & Shale	236'
Red Bed & Shale	430'
Shale & Lime	535'
Shale & Shells	658'
Shale & Lime	782'
Shale & Shells	972'
Shale & Lime	1091'
Shale & Lime Shells	1280'
Shale & Lime	1441'
Shale & Shells	1870'
Shale & Lime Streaks	2285'
Lime	2420'
Lime & Shale	2545'
Lime & Shale Streaks	2655'
Lime	2790'
Shale & Lime	2905'
Lime	3055'
Shale & Lime	3128'
Lime	3142'
Lime & Shale	3158'
Shale & Lime & Chalk	3295'
Lime & Chalk	3405'
Lime & Shale	3750'
Lime	4020'
Lime & Shale	4145'
Shale & Lime	4290'
Lime & Shale	4428'
Shale & Lime	4540'
Lime & Shale	4610'
Lime & Shale Streaks	4715'
Lime & Shale	4780'
Lime	4865'
Lime & Chalk	4935'
Lime	5095'
Sand	5105'
Lime	3890'
Shale	3898'
Lime & Shale Streaks	5930'
Lime	5950'
Shale & Lime	5977'
Shale & Sand	6002'
Lime	6055'
Lime & Shale (Core #1)	6105'
Lime	6163'
Rotary Total Depth	6163'

Set 5-1/2" casing at 6162' cemented with 200 sacks cement