


Total Depth. 6075'
 Comm. 11-21-57 Comp. 12-22-57
 Shot or Treated.
 Contractor.
 Issued. 4-19-58

County Meade

KANSAS



Elevation. 2229 RB

Production. 17,700,000 CFG

CASING:

10 3/4" 1122' w/575 sx cem.
 5 1/2" 6075' w/300 sx cem.

Figures indicate Bottom of Formations.

sand, red bed 100
 red bed, shells 1122
 Anhydrite, red bed, shale 1590
 red bed, anhydrite 1830
 shale, lime 1970
 gyp, salt w/lime, shale 2180
 gyp, lime, shale 2350
 anhydrite, gyp, lime 2445
 anhydrite, gyp 2590
 shale, lime 2730
 lime w/shale 2770
 lime, shale 2830
 lime, brkn 2946
 lime, chalk 2996
 chalky lime 3007
 chalk, gyp 3120
 chalky lime 3275
 lime, chalk 3345
 chalk, lime 3480
 chalky lime 3586
 chalk 3600
 chalky lime 3791
 chalk, lime, sand 3868
 shale, lime 4130
 sdy shale 4220
 shale 4325
 shale, lime 4463
 shale 4500
 lime 4589
 shale, lime 4695
 chalky lime 4748
 lime 4795
 brkn lime, shale 4804
 shale, lime, chalk 4936
 chalky lime 4977
 chalk, lime, shale 5046
 lime, shale 5070
 lime 5253
 lime, chert 5318
 shale, lime 5362
 lime 5660
 lime, chert 5674
 lime 5840
 lime, sand 5885
 sand 5891
 Morrow sand 5922
 sdy lime, shale 5937
 shale, lime 6001
 lime 6075
 Total Depth

Perf: 5894-5914'
 Acidized w/500 gals. M.H.
 Fr aced w/12,000 gals. gelled
 Diesel & 5000# sand.

TOPS:

Heebner
 Lansing, Kansas City
 Marmaton
 Morrow
 Morrow sand
 Mississippi

Sample SCHL
 4447 4444
 4635 4616
 5390
 5852 5850
 5880
 5940 5940