

KANSAS DRILLERS LOG

S. 35 T. 34 S. R. 26 W

API No. 15 — 119 — 20,351
County Number

Loc. C NW SW


Operator
Kennedy & Mitchell, Inc.

County Meade

Address
Box 1578 Liberal, Kansas 67901

640 Acres
N

Well No. 25-419 Lease Name Walker



Footage Location
1980 feet from (X) (S) line 660 feet from (X) (W) line

Elev.: Gr. 2209

Principal Contractor DaMac Drilling, Inc. Geologist

Spud Date November 12, 1979 Total Depth 6460 P.B.T.D. 6300

Date Completed November 28, 1979 Oil Purchaser

DF 2218 KB 2221

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface casing	12 1/4"	8 5/8"	24#	698'	35/65 pozmix class H	325 125	6% gel, 2% cc, 1/4# flakes 3% cc
production	7 7/8"	4 1/2"	10.5#	6460'	50/50 pozmix	50 200	8% gel, 10% salt, 12 1/2# Kolite 12 1/2# Kolite, 18% salt, .75% TIC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2 shots/foot	.38 DP	6370-6375'
TUBING RECORD			2 shots/foot	.38 DP	6034-6044'
Size	Setting depth	Packer set at			
2 3/8"	6009	6009			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
CAST IRON BRIDGE PLUG SET @	6300'
750 gal 15% MCA acid, using 15 ball sealers	6370-6375'
1000 gal 15% MCA acid	6034-6044'

INITIAL PRODUCTION

Date of first production shutin/waiting on PL connect on	Producing method (flowing, pumping, gas lift, etc.) flowing
RATE OF PRODUCTION PER 24 HOURS	Oil 0 bbls. Gas 400 MCF Water 20 bbls. Gas-oil ratio - CFPB
Disposition of gas (vented, used on lease or sold) to be sold	Producing interval (s) 6034'-6044' CHESTER

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
KENNEDY & MITCHELL, INC.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Gas Well

Well No.
25-419

Lease Name
WALKER

S 35 T 34 SR 26 ^{EX}
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface	0	308		
Red Bed and Shale	308	1653		
Shale	1653	1850		
Lime and Shale	1850	5270		
Lime	5270	6460RTD		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Ned E Lowry
Signature

Agent/Kennedy & Mitchell, Inc.
Title

May 10, 1980
Date