

# KANSAS DRILLERS LOG

API No. 15 — 119 — 20,351  
County Number

Operator  
 Kennedy & Mitchell, Inc.

Address Box 1578 Liberal, Kansas 67901

Well No. 25-419 Lease Name Walker

Footage Location  
1980 feet from (N) (S) line 660 feet from (E) (W) line

Principal Contractor DaMac Drilling, Inc. Geologist

Spud Date November 12, 1979 Total Depth 6460 P.B.T.D. 6300


Date Completed November 28, 1979 Oil Purchaser

S. 35 T. 34 R. 26  $\frac{N}{W}$

Loc. C NW SW

County Meade

640 Acres



Elev.: Gr. 2209

DF 2218 KB 2221

## CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface casing	12 $\frac{1}{4}$ "	8 5/8"	24#	698'	35/65 pozmix class H	325 125	6%gel, 2%cc, $\frac{1}{4}$ #flakes 3%cc
production	7 7/8"	4 1/2"	10.5#	6460'	class H	50	8%gel, 10%salt, 12 $\frac{1}{2}$ # Kolite
					50/50 pozmix	200	12 $\frac{1}{2}$ #Kolite, 18%salt, .75%TIC

## LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

## PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
2 shots/foot	.38 DP	6370-6375'
2 shots/foot	.38 DP	6034-6044'

## TUBING RECORD

Size	Setting depth	Packer set at
2 3/8"	6009	6009

## ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
CAST IRON BRIDGE PLUG SET @	6300'
750 gal 15% MCA acid, using 15 ball sealers	6370-6375'
1000 gal 15% MCA acid	6034-6044'

## INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
shutin/waiting on PL connect	on flowing				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	0 bbls.	400 MCF	20 bbls.	- CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
to be sold			6034'-6044' CHESTER		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator  
KENNEDY & MITCHELL, INC.

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:

Gas Well

Well No.  
25-419

Lease Name  
WALKER

S 35 T 34 S R 26 <sup>EX</sup>  
W

### WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Surface

0

308

Red Bed and Shale

308

1653

Shale

1653

1850

Lime and Shale

1850

5270

Lime

5270

6460RTD

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

*Ned E. Lowry*  
Signature

Agent/Kennedy & Mitchell, Inc.

Title

May 10, 1980

Date