


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- **SUN OIL CO.**
 Farm- **F. Walker** No. **1**

SEC. 35 T. 34 R. 26W
 SW SW NE

Total Depth. **6111'**
 Comm. **5-21-57** Comp. **6-15-57**
 Shot or Treated.
 Contractor.
 Issued. **8-16-58**

County **Meade**
 KANSAS



CASING:

8 5/8" 1228.26' cem w/1000 sx.
5 1/2" 6110' cem w/200 sx.

Elevation. **2203'**

Production. **1,485,000 CFG**

Figures Indicate Bottom of Formations.

clay & sand	40	4
red bed & lime	970	
shale, lime, anhydrite	1276	
lime & shaly lime	1402	
shale	1715	
lime & shale	1880	
lime	2508	
shale & lime	2828	
lime, strks shale	3957	
shale	4240	
lime & shale	4275	
limey shale	4457	
lime & shale	4542	
shale	4590	
lime	4635	
shale	4662	
lime	5858	
shale	5888	
lime	5895	
shale	5907	
sand & lime	5938	
shale & lime	5955	
lime	6111	
Total Depth		

TOPS:

Heebner Shale	4493
Lansing Lime	4662
Marmaton Lime	5361
Morrow Shale	5858
Morrow Sand	5907
Chester Lime	5955

DST #1 5962-6041', op 1 hr, gas 11 min.,
 33 MCFD. FP 95-110#, BHP 1570#. Rec.
 270' gas cut mud.

DST #2 6050-6111', op 3/4 hr, weak blow
 22 min., and died. Rec. 10' mud.
 FP 20-50#, BHP 85#.

Core #1 5901-5940' rec. 39'.