



State Kansas Field McKinney Gas
 County Meade
 Company Huber Corp.
 Farm Ediger Well No. 1
 Sec. 5 Twp 34S Range 26W
 fr N fr E fr S fr W
 of C NE $\frac{1}{2}$
 Contractor Rocket Drilling (PEPLFO)
 Remarks
 Comm. 2-14-55 Comp. 3-16-55
 Elev. 2295 T. D. 5930 P. B.
 Pay

T. R. D & A R. P.
 Casing Record: 13 $\frac{3}{4}$ 7
 20 10 $\frac{3}{4}$ 5 $\frac{1}{2}$
 16 8 $\frac{3}{4}$ 1400/900

	LOC	Tops	Sample
FEB 23 1955	<u>1075 no pipe</u>		<u>Mon 5743</u>
	<u>85 1400/900</u>		<u>MISS (st. km)</u>
	<u>DST 3018-3170 op 30mm</u>		
	<u>sh bto Tang 14 1970msw</u>		
	<u>FP 625.900 BH 1000</u>		
	<u>TTD 3274</u>		<u>schl</u>
	<u>3565</u>		<u>well. 1910</u>
	<u>5131</u>		<u>Well 2490</u>
MAR 9 1955	<u>TTD 5743</u>		<u>Well 2530</u>
	<u>pen to core</u>		<u>Wb 4/4 45</u>
MAR 16 1955	<u>5743-93 rev 48' 2oz 4/4 63</u>		
	<u>DST 5752-5820 14.40mm Long 4616</u>		
	<u>sh bto gun 53mm TSTM rev 100'</u>		
	<u>sh gcm. FPS-45 BH 1472/15</u>		<u>Mon 5729</u>
	<u>1'1" - sh</u>		<u>Mon sh 5740</u>
	<u>3'2" - tite 1m. sh. sl. sh.</u>		<u>Chs 5772</u>
	<u>2'6" - sh. sh.</u>		

Pat. Case on enclosed sheet!

2'6" - tile foss ls. w/sdy parting
1'1" - sh
3'8½" - tile sdy lm. w/streaks of md to fm sd w/
trace of por & sh. nodules
1'4" tile sd w/sli. tr. of por nodules
1'10" tile foss sdy lm w/sli. nodules
1'1" tile sd w/streaks of foss ls w/trace of
1.6" tile sdy ls
4'9" sh w/streaks md to fm gr sd
6'00" drk gray sdy sh
19'11" - hd tile ls. w/streaks drk gray sh.

DST 5752 - 5820 1 hr. 40 min
gr in 53 min test m
rec 100' sli'gcm FP 5-45
BH 1472/15

DST 5824 - 5930 open 1 hr. rec
85' very sli'gcm FP 45-60 BH 190/15

RTD 5930 run schl

D & A

Meade County, Kansas
J. M. Huber Corporation
PEPL Farm-Out

Ediger #1
Section 5-34-26
C of NE

Cored
5743-5793

Rec 48'

6'	1"	Sh	Dk gry micaceous platey calc
3'	2"	Ls	Tite, xln, tan-gry to drab partly sdy, foss, sli Glauc
0'	2 $\frac{1}{2}$ "		Fine shly sd to sdy grn sh
0'	2 $\frac{1}{2}$ "	Ls	Tite, med xln, tan to drab foss, partly sdy with trace chert
1'	1"	Sh	Grn platey & waxy
3'	8 $\frac{1}{2}$ "	Ls	Tite med-crs, tan foss, sdy w/thin grn sh partings w/streaks med-fine to fine subrounded sd, sli glauc w/trace poro & odor
1'	4"	Sd	Light, white, tite, med fine to fine colorless w/streaks grn sh trace poro & odor
1'	10"	Ls	Tite med crs, foss, tan, sdy w/trace chert, sli odor
1'	1"	Sd	Tite w/streaks med crs foss tan-drab ls, w/trace poro & odor
1'	6"	Ls	Tite med crs, foss tan to drab sdy w/some grn sh partings
4'	9"	Sh	Calc drk gry w/streaks med fine to fine light sd. and crs fossil frag
0'	10"	Sh	Drk gry, platey calc w/few crs fossil frag, sli sdy
19'	11"	Ls	Brn-drab hard tite dense xln w/streaks of drk gry calc sh embedded w/some fossil frag, bottom 2' 4" had vert frac