


State Kansas Field M. Kinney
Company Skelly & Aladdin County Muskegon
Farm Taylor No. 1
Sec. 22 Twp. 34.5 Range 26.0

Spot C E/2

Contractor WENTWORTH

Remarks



Comm. 8/25/56 Comp. 10-27-56

Elev. DF 2312 GL KB TD 607.9 PB

Pay 59.40-58

I.P. 998 MCF Press. CP 225
5.6 P 1850

Casing Record: 13 3/8 7"

20" 10 3/4 5 1/2" 60.73/250

16" 8 5/8 890/450

	Sample	Log
W.D. <u>8 5/8 890/450</u>	<u>Sand 4707</u> ✓	<u>Heeb 4544</u>
<u>W.D.</u>	<u>Marw 5375</u> ✓	<u>Law 4710</u>
<u>SEP 5</u> <u>φ 3040</u>	<u>Ck 5602</u> ✓	<u>Marw 5404</u>
<u>SEP 12</u> <u>φ 4790</u>	<u>Mot 55 5930</u> ✓	<u>cher 5614</u>
<u>SEP 19</u> <u>φ 5507</u>	<u>Chest 5960</u> ✓	<u>Marsh 5896</u>
<u>SEP 26</u> <u>φ 5915-54 MC 35'</u>		<u>" sd 5933</u>
<u>5' shale</u>		<u>chest 5987</u>
<u>7' low. brn. med to crs. sh.</u>		
<u>2' low as above glue.</u>		
<u>1' sh.</u>		
<u>3' sd. green fn gr. glue.</u>		
<u>sl. por. sl. sh. gas</u>		
<u>5' low. brn crs. sh. med. sh.</u>		
<u>1' low as above sd.</u>		
<u>4' sd. green to gr. fn gr. glue.</u>		
<u>glue. very shaly sl. por.</u>		
<u>7' sd. gr. y. fn gr. sh. lite v shly glue. sl. sh. gas</u>		
<u>1/2' sh</u>		
<u>1/2' LM. tan med sh. foun. (NS)</u>		
<u>DST 5896-5954 op 1 hr. wd to 50' dwd MC 20'</u>		
<u>Mud FP 35- BHP 230/20</u>		
<u>DST 5950-6014 op 1 hr. wd to T.O. rec 90' sl.</u>		
<u>Watery mud FP 75-125 BHP 825/20</u>		
<u>φ 6062</u>		

OCT 3 - DST RTD 6074 1 hr log
DST 6010-74 of 1 hr. rec 20' mud
FP40 - BHP 540/20 5 1/2 to 6073/250
RBD to 6035 PB to 5994 pf 66/5940-51
A/50 m. A/500 g 22 MCF. pf 16/5954-58
pf 1/5945 g 22 MCF.
OCT 10 Kns/10,000 from 30,000 rd/30,000 Kns/14,000
Subbed load g 549 MCF 51 24 MCF
g 972 MCF 51
OCT 17 ✓
OCT 24 PATD 5999 24 hr g 998 MCF thru 2" T
C P 225 24 hr SIF 1850.

AMARILLO TOPS

2314 KB

Winfield 2800 (-486)

Heebner 4544 (-2230)

Douglas 4554 (-2240)

Lansing 4710 (-2396)

Morrow 5896 (-3582)

Morrow Sd 5933 (-3619) T 14' b, por 5' b, g 998 MCF

Chester 5960 (-3646)

TD 6074 (-3760)