


*

State Ks Field McKINNEY
 Company SKELLY County MEADE
 Farm H. TAYLOR No. 1
 Sec. 28 Twp. 34 Range 26
 Spot 12.50' FN & EL CNE. LS.
 Contractor GRAHAM - MICH
 Remarks 6200'



Comm. 12-17-57 Comp. 2-5-58
 Elev. DF 2333 GL 2325 KB TD 6124 PB 6103
 Pay MOR 5977-90 MISS 6052-70
\$ 6086-79
I.P. 2 in. BD g. 7,600 MCF Press. S.I.S.P. 1660
 Casing Record: 13 3/8 7"
20" 10 3/4 5 1/2" 6124/300
16" 8 5/8 1110/675

	Sample	Log
176	HEED 4571	HEED 4572
JAN 1 LC @ 580 \$ 611	LAN5 4742	LAN5 4740
38 \$ 4010	MARM 5440	MARM 5440
JAN 8 \$ 5215	CHEER 5640	CHEER 5643
JAN 15 LC @ 5673	MOR 5932	MOR 5934
TTD 5964 prep to	" sd 597696	" sd 597696
\$	CHESTER 6016	CHESTER 6011
JAN 22 \$ 5964-98		
rec 29 1/2' 2 1/2' ls, 1/2' sh,		
1' ls, 2' ls, 4 1/2' lost, 1' ls,		
3' sd, 1' sd, 2' sd gd pos,		
5' sh, 1' sh, 1' sd, 1' sd		
2' sd, 3' ls, 1' ls, 2' sd		
slt odor from 5926-98		
DST 5973-98		
op 1' 15" GTS 11"		
g 146 MCF/17" g 286 MCF/1' 15" rec 180' GCM		
FP 100-155 BHP 2115/20"		
DST 5996-6060 op 1 in. GTS 10"		
g 112 MCF/25" g 133 MCF/60" rec 190' GCM		
FP 50-110 BHP 1870/20"		
DST 6081-6124 op 1 in. GTS 5" g 398 MCF/15"		
g 589 MCF/1 in. rec 210' GCM FP 170-255		
BHP 2050/20 RTD 6124 ran log 5 1/2 in.		

JAN 29 MIST CO 6105 pf 52/6086-99
g 520 MCF MA/500 3hr BD g 2,120 MCF
(dry) 5 1/2 hr SIP 1560 A/3000
A/2080 (7 1/2) 5 1/2 hr BD g 3,920 MCF + load
pl @ 6078 pf 108/6052-70 g 250 MCF
MA/500 3hr BD g 4,400 MCF A/5000
A/2000 (7 1/2) drove pl to 6104
PB @ 6013 pf 65/5977-90 MA/500
g 416 MCF + wt ^{FR/5000} ^{PR/5000} ^{PR/5000} ^{PR/5000} ^{PR/5000} ^{PR/5000} ^{PR/5000} ^{PR/5000} ^{PR/5000} ^{PR/5000}
g FCP 810 ~~ST~~ g 4,800 MCF (dry)
FEB 5 24hr SICP 1660 2hr BD g 3,600 MCF
FCP 1000

CF

AMARILLO TOPS

2336 KB

Heebner 4578 (-2242)

Lansing 4736 (-2400)

Morrow 5934 (-3598) T 68', 22' Tss

"S-2" Sd 5977 (-3641) T 22', por 17', T 416 MCF / XW

Chester 6002 (-3666) tst'd 7,600 MCF

TD 6124 (-3788)