


*
 State KS Field M'Kinney
 Company Tenn. Gas Trans. County Meade
 Farm Danielson No. 1
 Sec. 24 Twp. 34 Range 26
 Spot c w 1/2
 Contractor Capitt
 Remarks p.d. 5800



Comm. 4-12-57 Comp. 6-25-57
 Elev. DF 2177 GL 2192 KB TD 5937 PB 5844
 Pay MOR 5797-99 ~~MISS 5872-84~~

I.P. COF 1,300 MPF Press. SICP 1120
 Casing Record: 13 3/8" 7"
 20" 10 3/4" 5 1/2" 5934/200
 16" 8 5/8" 1166/525

	Sample	Log
APR 10 ✓	<u>salt 440</u>	<u>nan 5764</u>
APR 17 5811	<u>Lan 4590</u>	<u>miss 5811</u>
858	<u>MOR 5767</u>	
Ø 1600	<u>COMP. MOR 5760</u>	
APR 24	<u>MISS 5811</u>	
Ø 3692		
MAY 1 Ø 5220		
MAY 8		
Ø 5770-5810 rec 33'		
12'sh, 5'45, 3'sd, 5'sd, PP		
6'sd, 9d 600r,		
DST 5750-5810 op 2		
9ts 7", g 311 in 2 hrs,		
rec 180' gcm FPI 15-150		
BHP 1880/30		
Ø 5810-21 Apr 11'		
11' Ls Tan,		
Ø 5901		
MAY 15 DST 5817-5937, op 1 hr 15" rec 1080' in		
all press 0 (CPK failed)		
RTD 5937 ran log		
5 1/2" MICT		
MAY 22 BUILT CO 5848 ran 61R. PF 48/		
5872-84 over		

A/2000 swab N.S. p/c 5844 Rf 12/5797-99
24/5803-07 12/5809-11, A/500 m swab
S.G. est 200 MCF run T Fc/10000 sd/10000
Swab g 1,570 MCF FTP 700 FCP 875
12hr BD 940 MCF, ~~TST~~

MAY 28 g 720 MCF, SITP 1000 SICP 1140

~~SI~~
JUN 5 FTP 250, FCP 425, g 600 MCF thru 22/64" ck.
SICP 1120, SITP 962 ~~TST~~

JUN 12 ~~SI, 1120 T~~

JUN 18 ✓
JUN 26

~~PBTD 5892 COF 13 MCF PD~~
COF 1,300 MCF PD

Φ

AMARILLO TOPS

2180 KB

Heebner 4414 (-2234)

Douglas 4424 (-2244)

Lansing 4586 (-2406)

Morrow 5766 (-3586)

"S-2" Sd 5790 (-3610) T 20', por 6', tst'd 940 MCF

Chester 5848 (-3668)

TD 5937 (-3757)