


11-237W MAP NO. FR & COMP - UWWO LOC. 20-345-22W
 STATE Kans COUNTY Clark LOC. C SE
 OPER **Braham-Michaelis - Wichita, Kansas** FT/FR LINE
 WELL 1-26 FARM Randall FT/FR LINE
 POOL Snake Creek ELEV. 1880 GR 1887 DF 1890 XB
 CONT. Co. tools GEOL.
 CO. INT.

F.R. 11-6-64 SPUD 9-17-63 COMP 11-17-64
 TD 5729 FM St Gen PBTD

Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
		Morrow	5534-72	152	



Cal Flow 171 BOPD, Gr NA and SWDW in Glor sd perfs 750 - 1180 DUAL COMPLETION
 8 5/8" @750 w/450 sx. 4 1/2" @5728 w/200 sx.

Dada Inc.

(KB Log - Old)	OLD INFO: (Same Operator)
Lans 4518 -2628	DST #1 (Mrw sd) 5473-5550, Op 60", GTS/
Mrw sh 5468 -3578	immed, Ga 7,116,000 Cfgpd/15" and Stab,
Mrw sd 5532 -3642	R no flu, ISIP 1860#/30", IFF 909#,
Chest 5599 -3709	FFP 1120#, FSIP 1856#/30", <u>RTD 5729</u>
St Gen 5706 -3816	(St Gen), Log, 4 1/2" @5728 w/200 sx.,
* (Cont Below)	MICT, Perf Mrw sd 152/ <u>5534-72</u> , 1000A &

LTD 5729 -3839 Frac 7000 gal flu x 7000# sd, Rec ld,
 RTD 5729 -3839 Flo 150 BOPD, GOR 900:1, Cal Flo 171
 BOPD (16/64" choke), FTP 380#, SICP
 1346#, GOR 585:1, Mrw 5534-72 (State Pot) - Comp 3-10-64
NEW INFO: Pull tbg, Perf Glor sd 750-1180, No treatment, Inj Rate
 satisfactory, Ran 2" tbg w/pkr below Glor sd perfs to prod Mrw,
 Inj SW thru annulus, Dual Completion - Cal Flo 171 BOPD, Mrw
5534-72 and SWDW in Glor sd perfs 750-1180 - FIRST REPORTED AND
COMPLETED

P+A 3-22-65