


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
505 East Murdock, Wichita, Kansas

Company- **SKELLY OIL COMPANY**
 Farm- **Ida Bohling** No. **1**

SEC. 10 T. 34 R. 27W
C SW SE
1980' fr BL, 660' fr SL
of SE/4

Total Depth. 6050'
Comm. 6-12-59 Comp. 7-6-59
Shot or Treated.
Contractor. Graham-Michaelis Drlg.
Issued. 9-26-59

County Meade KANSAS



CASING:
8 5/8" 1379' cem w/900 sx.

Elevation. 2381' DF

Production. Dry

Figures Indicate Bottom of Formations.

sand & clay	200
sand & red bed	871
red bed & shale	1280
shale & anhydrite	1380
shale	2111
shale & lime	4003
shale	4285
shale & lime	4345
shale	4500
lime & shale	4989
lime	5769
lime	5823
lime & shale	5910
lime	5926
lime & shale	5955
lime	6011
lime & shale	6039
lime	6050
Total Depth	

FFP 470#, FBHP 1390#/20 mins.

Ran Schlumberger Survey.

TOPS:

Council Grove	3093
Heebner Shale	4480
Toronto	4498
Lansing Lime	4656
Marmaton	5340
Cherokee	5537
Morrow	5847
Morrow Sand	5860
Chester	5953

DRILL STEM TESTS: HALLIBURTON

#1 packer set at 5735', used 34' anchor, op 1 hr., no blow, rec. 5' drilling mud, IBHP 190#/20 mins., IFP 20#, FFP 20#, FBHP 45#/20 mins.

#2 packer set at 5835', used 75' anchor, op 1 hr., no blow, rec. 5' drilling mud, IBHP 190#/20 mins., IFP 25#, FFP 45#, FBHP 45#/20 mins.

#3 packer set @ 3919', used 36' anchor, op 1 hr., weak blow for 5 mins, rec. 30' drilling mud, IBHP 66#/20 mins., IFP 31#, FFP 31#, FBHP 66#/20 mins.

#4 tried to drill stem test, packer set at 5965', used 46' anchor, op 50 mins., packer began leaking in 15 mins., gas to surf. in 25 mins., gas gauged 169 MCF in 30 mins., 133 MCF in 45 mins., rec. 3240' drilling mud, no pressures.

#5 packer set at 5980', used 70' anchor, op 1 hr., gas to surf. in 20 mins., gauged 25,830 cu. ft. in 40 mins., 25,830 cu. ft. in 1 hr., rec. 690' heavily gas cut mud, 180' muddy salt water, and 300' salt water. IBHP 2110#/20 mins., IFP 340#.