


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **THOMAS-BREWER & ALAMO CORP.**
 Farm- **P. F. Isac** No. **1**

SEC. **12** T. **34** R. **27W**
 C SE NE

Total Depth. **6175'**
 Comm. **4-15-57** Comp. **5-14-57**
 Shot or Treated.
 Contractor. **Midwestern Drillers, Inc.**
 Issued. **5-17-58**

County **Meade**
KANSAS



CASING:

13 3/8" 280' cem w/275 sx.
8 5/8" 2645' cem w/200 sx.
5 1/2" 6090' cem w/150 sx.

Elevation. **2440' RB**

Production. **Dry**

Figures indicate Bottom of Formations.

surface sand, clay, red bed	300
red bed, gypsum & shale	1025
sand, shale & gypsum	1315
gypsum and shale	1565
shale, gypsum & red bed	1740
Anhydrite, gypsum & shale	1953
Anhydrite	2145
shale, Anhydrite and gypsum	2306
Anhydrite	2420
shale & Anhydrite	2515
Anhydrite	2650
dolomite	2745
dolomite & shale	2900
lime & shale	3020
dolomite	3125
lime & shale	3385
dolomite	3525
lime & shale	3940
lime	4025
lime & shale	4809
lime & chert	4885
lime	4945
lime & shale	5050
lime	5080
lime & shale	5162
lime	5285
lime & shale	5390
lime	5450
lime & shale	5490
lime, shale & chert	5545
lime & shale	5634
lime	5720
lime & shale	5795
lime	5825
lime & shale	5920
lime	5970
lime & shale	6012
lime	6100
lime	6175

TOPS: SCOUT

Heebner	4567
Toronto	4601
Lansing	4758
Marmaton	5462
Cherokee	5578
Morrow	5909
Chester	5969

DST #1 @ 6012'
 DST #2 @ 6100'
 DST #3 @ 6175'
 DST #4 @ 6175'

Total Depth