


KANSAS CORPORATION COMMISSION

WELL RECORD

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)



Lease Name: Baragree #1-19 Well No. 1-19
 Well Located: C N/2 S/2
S1C 19 TWP 34S RGE 27W
 Operator: The Headington Company
 Address: 801 First National Center, Okla. City, Okla.
 Elevation: Ground 2393 D.F. 2402 K.B.
 Type Well: (Oil, gas, dry hole) Gas

Drilling Commenced: 8-22-73 19 Drilling Completed: 9-5-73 19
 Well Completed: 2-26-74 19 Total Depth 6280'
 Initial Production: 1,200 MCF

Casing Record

Size: 4-1/2" Set at 6264 Size: _____ Set at _____
 Size: 8-5/8 Set at 1307 Size: _____ Set at _____

Liner Record

Size: None Set from _____ To _____

Cementing

<u>Casing Size</u>	<u>Sacks</u>	<u>Type Cement and Additives</u>
<u>4-1/2</u>	<u>100</u>	<u>2% gel, 10% salt - gilsonite - regular</u>
<u>8-5/8"</u>	<u>600</u>	<u>Reg. 3% cc, posmix 6% gel, 2%cc.</u>
_____	_____	_____

Perforations

<u>Formation</u>	<u>Perforated Interval and Number Shots</u>	
_____	_____	_____
<u>Chester</u>	<u>6102 - 6112</u>	<u>20 holes</u>
_____	_____	_____

Electric Log Run (Show type log and depths covered)

Dual Induction 1307 - 6280

(Fill in formation and related information on reverse side)

FORMATION, TESTING AND COMPLETION RECORD

19-34-27w

Show Drill Stem Tests,
Well Stimulation and
Production Tests

Formation	Top	Bottom	
Sand, Clay	0	105	
Sand, Red Bed	105	850	
Anhydrite	850	1980	
Anhydrite, Shale	1980	2450	
Shale, Lime	2450	5925	
Lime	5925	6280'	