

KANSAS DRILLERS LOG

API No. 15 — 119 — 20,212
County Number

S. 32 T. 34 R. 27 ^E/_W

Loc. 70' N/C SL/SE


Operator
 The Headington Company

County Meade

Address
 2820 Liberty Tower Oklahoma City, Oklahoma 73102

640 Acres
 N

Well No. #1-325 A Lease Name Thonhoff OWWO



Footage Location
 70' N. of Center of South Line of SE/4
feet from (N) (S) line feet from (E) (W) line

Elev.: Gr. 2333

Principal Contractor Unit Drilling Company Geologist Edward Headington

Spud Date 9-28-75 OWWO Total Depth 6250' P.B.T.D.

Date Completed 11-5-75 Oil Purchaser OWWO - Gas Well

DF 2340 KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Casing	7-7/8"	4-1/4"	10.5	6250	4% gel Reg. 15% salt 12.5 gilsonite	125 sax.	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None			2 - 19 holes	19 holes	6120-6129'

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8"	6108'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Spotted 500 gallons acid. Treated with 10,000 gals. Westpad and 10,000 gal. Series 70 15% acid.	6120-6129'

INITIAL PRODUCTION

Date of first production <u>Not connected to pipeline</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Flowing</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>-0-</u> bbls. Gas <u>390 MCF</u> MCF Water <u>-0-</u> bbls. Gas-oil ratio <u>-0-</u> CFPB
Disposition of gas (vented, used on lease or sold) <u>Sold</u>	Producing interval (s) <u>6104-6154'</u>

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. #1-A	Lease Name Thonhoff	Gas Well
S <u>32</u> T <u>34S</u> R <u>27</u> ^W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand & Native Clay	0	160		
Red Bed	160	523		
Red Bed & Shale	523	945		
Red Bed, Sand & Shale	945	1510		
Sand & Shale	1510	2280		
Shale & Anhydrite	2280	2510		
Shale & Lime	2510	6250		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Date Received	<i>Laverne Moberly</i> Signature
	Engineering Department Title
	11-6-75 Date