


2-228W MAP NO. K-85 SEC. 1-34S-27W  
 STATE Kans COUNTY Meade LOC. C NW SE  
 OPER. Oil & Gas Property Management - Houston, Texas FT/FR \_\_\_\_\_ LINE \_\_\_\_\_  
 WELL 1 FARM Henry Classen FT/FR \_\_\_\_\_ LINE \_\_\_\_\_  
McKinney Fld Ext (Miss & Mrw) LEV. 2444 GR. 2454 DF 2456 KB  
 CONT. Wakefield (Gas) GEOL. Bill Atkinson  
 CO. INT. \_\_\_\_\_  
 F.R. 2-1-65 SPUD. 2-2-65 COMP. 2-25-65  
 TD. 6156 FM. Chest PBD. \_\_\_\_\_



COMP. RECORD \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_ D&A \_\_\_\_\_

*Data Inc.*

8" @1460 w/675 sx & 100 sx  
 (KB Log) DST #1 (Mrw) 5887-5960, Op 60", R 10' M,  
 Shaw Gr not called ISIP 492#/30", IFP 18#, FFP 36#, FSIP 402  
 Wre 3059 - 603 #/30"  
 Lans 4754 -2298 DST #2 (Chest) 5959-6052, Op 60", GB/60",  
 Marm 5403 -2947 No Gas, R 30' M, ISIP 146#/30", IFP 18#,  
 Chero 5600 -3144 FFP 36#, FSIP 346#/30", RTD 6153, Log,  
 Mrw 5897 -3441 WLT #1 (Shaw Gr) 3635½-38, Plugged, no  
 Chest 5960 -3504 rec, no press  
 6153 -3697 WLT #2 (Shaw Gr) 3638 (only), Op 90", No  
 6156 -3700 ISIP taken, SP less than 100#, R 2000 Cf

\$W, No Gas, FSIP less than 100#  
DST #3 (Chest) 6075-6156 (By Log), Op 60", VWB/25", By passed  
 tool, R 108' M, ISIP 1164#/30", IFP 67#, FFP 75#, FSIP 224#/30",  
D&A (2-20-65) - COMPLETED

LIBERAL ELECTRIC LOG TOPS

2456 KB

Winfield 2808 (-352)  
Heebner 4586 (-2130)  
Toronto 4602 (-2146)  
Lansing 4754 (-2298)  
Marmaton 5404 (-2948)  
Morrow 5898 (-3442) DST Mud  
Chester 5960 (-3504) DST Mud  
TD 6153 D & A