


State K.S. Field W.C.
 Company Thomas S. Brewer & Sons County Meade
 Farm Isaac No. 1
 Sec. 12 Twp. 34 Range 27
 Spot C.S.E., N.E.
 Contractor Midwestern
 Remarks FD 6300, Westhouse F.D.
Miller, sunny, skelly own
 Comm. 4-16-57 Comp. 6-18-57
 Elev. DF 2436, GL 2430, KB TD 6175 PB
 Pay D & A



I.P. Press.
 Casing Record: 13 3/8 280/275 7"
 20" 10 3/4 5 1/2" 6090/150
 16" 8 5/8 2650/200

	Sample	Log
RUR	Heel 4567	Heel 4567
APR 24	TOR 4588	TOR 4601
Spud	Lam 4755	Lam 4758
1378		Norm 5462
890		Chas 5578
3264		Norm 5909
MAY 1 3940		Chas 5969
MAY 8 5555		
MAY 15 DST 5980-6012 op1		
gts 47' TST, rec 10' ccm		
FP 25-85, BHP 1275/20		
DST 6012-6100 op 1 hr,		
rec 10' ccm FP 115-125		
BHP 155/20		
DST (ST PK) 5903-92 op1		
rec 80 m FP 115, BHP 115/20		
DST 6150-75 op 30 sec 10' m		
FP 0, BHP 0/20		
RTD 6175 run log prep run 59		
MAY 22 5' @ RUT CO 6058 run 61R		
PF 52/6004-17, 16/6030-34 24/6038-44		
A/500 swab 975 MCF A/3000 g 285 MCF		
Prep Fr.		

over

MAY 28 fr/20000 SN/10000 fl/1000
g 809MIF lat g 380MIF A/1000 (7½)
TST

JUN 5 g 382MIF SICP1450 TST

JUN 12 RUC 2½h BD 950MIF CO 6050

pk 5975 sg/500g plastic Prep re sg

JUN 18 Sg/110 CO ? PF 24/6038-44

A/6000 swab SIP 400

~~prep~~ D & A

AMARILLO TOPS

2440

Winfield 2796 (-356)

Heebner 4584 (-2144)

Douglas 4592 (-2152)

Lansing 4760 (-2320)

Morrow 5908 (-3468)

"S-2" Sd 5940 (-3500) T 8', por 7', NS

Miss 5969 (-3529)

TD 6175 (-3735)