


4-58W MAP NO. REPL. COMP. SEC. 15-34S-27W
 STATE Kans COUNTY Meade LOC App C NW/4
 OPER. Skelly Oil Co., Wichita, Kansas 1265 FT/FR W LINE
 WELL 1 FARM Charles Merkle 1375 FT/FR S LINE
 McKinney ELEV. 2374 GR. 2381 OF 2382 KB
 Gabbert-Jones Drlg. GEOL. Bob Dickinson of NW/4
 CO. INT. 6100' Gas Test
 F.R. 1-28-63 SPUD. 1-29-63 COMP. 4-2-63
 TD. 6090 FM. Chester PBTD.
 8 5/8" @1386/400 sx. D&A
 (KB Spl) (KB Log) Data Inc.



St Corr	1346	+1036	CG	3105	- 723
Lans	3685		Tor	4515	-2133
Marm	5375		Lans	4660	-2278
Chest	5356		Marm	5357	-2975
Morr	5875		Chero	5561	-3179
Morr sd	5935		Morr sh	5877	-3495
Chest	5960		" sd	5937	-3555
RTD	6090		Chest	5970	-3588
			LTD	6090	-3708

DST #1 (Morr) 5903-60, Failed

DST #2 (Morr) 5861-5960, Op 1 hr, GB/1 hr, R 500' SGC & MSW + 2373' SGCSW, IBHP 1927#/30" IFP 570#, FFP 1490#, FBHP 1802#/30" DST #3 (Chest) 6021-6051, Op 1 hr, WB/26", R 25' M, IBHP 32#/30", IFP 20#, FFP 20#, FBHP 32#/30", RTD

6090, Sj Log

Sj WLT #1 (Lans) 4986-4988½, Op 90", No Gas-No Oil-No Dist, R 15,400 cc filt wtr, ISIP 1900#/7", SP less than 50#, FSIP 1870#/6", Shot Gas=1.03 Cfg, Solution Gas .00 Cfg, Free Gas .00 Cfg, Total Gas 1.03 Cfg, Est Prod by Sj, Wtr 4986-4988½ (Lans), Por 13-15%, Water Sat 23-27% from 4726-4728½ (Lans), Por 15%, Wtr Sat 45%, Sj WLT #2 (Lans) 4726-4728½, Op 60", R Scum of heavy oil (29 deg) + 17,400 cc filt wtr, Shot Gas 1.13 CF, Soutlion Gas .00 CF, Free Gas .004, IBHP 1900#/48 sec, SP 0#, 430#, FBHP 1900#/4", Re-Take WLT #2 (Lans) 4726-4728½, SI 6", Op 35", R 2600 cc oil (Gr 29 deg) + 2000 cc MCO + 16,000 cc filt wtr, IBHP 1930#/30 sec, SP 0#, 180#, FBHP 1930#/3", 4½" 4801/150 sx., Perf 12/4725-28 (Lans), \$ 12 GO + 10 BW/1 hr, \$ 100 BSW + scum dead oil/10 hrs, 150A, \$ 147 BFW/7 hrs + SSO & G, Sq 4725-28 w/75 sx., Notch 4727 (Lans) \$ 5 hrs, No oil, wtr or Gas, 250A w/oil ld, \$ 43 BLO/1 hr, \$ 33 BLO + 70 BSW/4 hrs, \$ 84 BSW w/sli scum oil + tr Gas /4 hrs, D&A COMPLETED (3-19-63) REPL. COMP. (4-20-63) CORR: Correct Interval on DST #3 to 6021-50

AMARILLO ELECTRIC LOG TOPS

2383 KB

Winfield 2753 (-370)
 Heebner 4499 (-2116)
 Toronto 4514 (-2131)
 Lansing 4660 (-2277) \$ XW w/SSO&G
 Marmaton 5357 (-2974)
 Morrow 5875 (-3492)
 "S-2" 5937 (-3554) 21/26; DST/SGCXW
 Chester 6008 (-3625) DST/Mud
 TD 6090 D & A