


State Kansas Field Barragreed
Company Skelly Oil Company County Meade
Farm H. L. Ellegde No. 1
Sec. 26 Twp. 34S Range 28W

Spot C NW SE

Contractor Chas. Hume 3200':C.G.

Remarks _____



Comm. 7/31/59 Comp. 8/19/59

Elev. 445 DF 2387 GL _____ KB _____ TD 3122 PB _____

Pay _____

DEA

_____ I.P. _____ Press. _____

Casing Record: 13 3/8 _____ 7" _____

20" _____ 10 3/4 _____ 5 1/2" _____

16" _____ 8 5/8 794/500 _____

LOCATION	Sample	Log
<u>AUG 5 sp? csg #2035</u>	<u>CG 3080</u>	<u>C.G. 673 3060</u>
<u>AUG 12 E 3056-77</u>		
<u>rec 21'</u>		
<u>6' ls dns</u>	<u>C50</u>	<u>337</u>
<u>4' sh grn</u>	<u>win 2724</u>	<u>567</u>
<u>3' sh red</u>	<u>(Gore 2954-567)</u>	
<u>1' ls grn sh incl</u>		
<u>1' ls fass poor por</u>		
<u>vert kc</u>		
<u>1' ls silic</u>		
<u>3' sh red</u>		
<u>2' ls dns</u>		
<u>DST 3031-77 qd 1'</u>		
<u>rec 335 mcxw + 90'xw</u>		
<u>16IP 1410/20" FP 125-225</u>		
<u>FSIP 1140/20</u>		
<u>E 3078-3104 rec 26'</u>		
<u>2' sh dk gy</u>		
<u>4' ls tite</u>		
<u>1' ls silic v hard tite</u>		
<u>7' ls vert fx, tr str,</u>		
<u>poor por</u>		
<u>1' ls lfgy rag por wth</u>		

8' ls v foss oöl fr per.

3' ls tile

DST 3080-3104 gp 1' rec

87' may XW 1SIP 920/20

FP 35-70 FSIP 820/20

- E 3104-22 pulling tool.

AUG 19 E 3104-22 rec 17.5'

2.5' ls med-dk gr, sh stks

1.5' ls buff-gr dng fa-xtln
foss silic.

1' sh red & green

10.5' ls lt gr v foss oöl tr glauc.
get to fair per

2' ls dng gg to buff v foss
fn xtln silic

DST 3102-22 gp 1 hr. fr blk T.O.

rec 1170' XW 1SIP 920/20

FP 105-550 FSIP 885/20

RTD 3122 log.

D & A