

229W

MAP NO.

K-85

SEC. 27-34S-28W

STATE Kansas COUNTY Meade

LOC. App C SW

OPER Imperial Oil Of Kansas - Wichita, Kansas

1250FT/FR S LINE

WELL #1 FARM Meierdierks

J5 1250FT/FR W LINE

WC

ELEV. 2424 GR 2429

DF 2431 KB

CONT. Chem-Tech Drlg.

GEOL. Gordon Keen

of SW/4

CO. INT. 3100' CG Test

FR. 6-1-64

SPUD.

6-1-64

COMP.

10-20-64

TD. 4598

FM.

Tor

PBD.

Completion
Record

PRODUCING FM.

FROM

TO

PERF
W/HOLES

TREATMENT

Coun Grove

3101-3106

20

10,500A

Est Ga: 3,120,000 CFGPD

Casing
Record

WC-2 1/2 mi W of Barragrey (CG Gas)

7" @1406' w/400 Sx.

4 1/2" @3348' w/75 Sx.

Data Inc.

(KB Spl Tops:)

Anh 1358 /1073

CG 3084 - 653

RTD 4598 -2167

(KB Log Tops:)

Winf 2747 - 316

Wre 2978 - 547

CG 3084 - 653

Hb 4478 -2047

Tor 4512 -2081

LTD 4598 -2167

DST #1 (CG "A" & "B") 3075-3107, Op 30", GTS/2", TSTM, Ga 400,000 CFGPD/7", Ga 680,000 CFGPD/15" & Stab, R 120' GCM & 60' GCWM, ISIP 895#/20", IFP 111#, FFP 149#, FSIP 895#/20", DST #2

(CG "C") 3108-20, Op 30", R 120' SW, ISIP 895#/20" IFP 0#, FFP 74#, FSIP 895#/20", DST #3 (CG "D") 3120-40, Op 1 hr, GTS/4", Ga 180,000 CFGPD/7" Ga 100,000 CFGPD/10", Ga 100,000 CFGPD/60", R120' SW, ISIP 857#/20", IFP 37#, FFP 74#, FSIP 857#/20", DST #4 (CG "E") 3124-75, Op 1 hr, R 1870' SW, ISIP 932#/20", IFP 223#, FFP 895#, FSIP 932#/20", DST #5 (CG) 3209-55, Op 1 hr GTS/5", Est Ga 60,000 CFGPD, R 660' foamy GCM & 180' SW, ISIP 932#/20", IFP 111#, FFP 260#, FSIP 857#/20", Ran 1st log, 4 1/2" @3348' w/75 Sx. Perf (CG) 20/3128-33, \$ dn, SSG/2 hrs, SI/12 hrs, open w/blo gas, TSTM, no flu, 500A, 20 BWPH/3 hrs w/some gas, Sq 3128-33 w/75 Sx Perf (CG) 20/3101-06, \$ dn, No flu/3 hrs, Ga 30,000 CFGPD thru 1" choke, 500A, SI/12 hrs; blo dn & Ga 2,718,000 CFGPD & small amt flu, 10,000A, Max Press 300#, Inj 5 1/2 BPM, Pull \$ 5 times & flo, Rec 1d, Flo 24 hrs, (Test 18# on 30# ga) Ga Est 3,120,000 CFGPD, Est Ga 3,120,000 CFGPD, SIGW CG 3101-06 - COMPLETED 10-13-64

CS 2

Win 2746-1357

CG Grove 2976 + 545

Log in Prod File