


12-222W MAP NO. K-84 SEC. 34-34S-28W
 STATE Kans COUNTY Meade LOC C SW NE
 OPER. Imperial Oil of Kansas Inc. - Wichita, Kansas FT/FR _____ LINE _____
 WELL 1 FARM Rhodes f-2399 FT/FR _____ LINE _____
Meierdierks Ext ELEV. 2396 GR. 2400 DF 2402 KB _____
 CONT. Co. tools GEOL. Bill Sladek
 CO. INT. 3200' Perm Test
 F.R. 10-13-64 SPUD 10-14-64 COMP. 12-22-64
 TD. 3286 FM. CG PBD. 3150 est
 CG 3061-3113 24 1800A
 4 Pt Ind OF: 10,000,000 Cfgpd
 8 5/8" @1307 w/650 sx. 4 1/2" @3265 w/150 sx.



Data Inc.

(KB Spl) DST #1 (CG) 3046-71, Op 2 hrs, GTS/4",
 Anh 1301 /1101 R 65' M, Ga 734,000 Cfgpd/5", Ga 1,540,000
 GG 3058 Cfgpd/20", ISIP 898#/15", IFP 124#, FFP
 RTD 3285 124#, FSIP 869#/15"
 (KB Log) DST #2 (CG) 3072-90, Op 1 hr, GTS/50",
 Winf 2718 - 316 TSTM, R 45' M, ISIP 820#/15", IFP 19#,
 Wre 2954 - 552 FFP 19#, FSIP 674#/15"
 CG 3059 - 657 DST #3 (CG) 3086-3112, Op 90", GTS/5", Ga
 RTD 3286 - 884 734,000 Cfgpd/16 & 90", R 450' SW, ISIP
 908#/15", IFP 144#, FFP 278#, FSIP 879#/
 15"

DST #4 (CG) 3210-28, Op 1 hr, GTS/5", TSTM, R 90' WM, ISIP 957#/
 15#, IFP 38#, FFP57#, FSIP 927#/15", RTD 3285, Log, 4 1/2" @3265 w/
 150 sx., MICT, CO est 3150, Ran GRN Log, Pf 8/3111-13 (CG), § dn,
 NSG/3 hrs, 500A, Ga 4,260,000 Cfgpd/4 hrs, Ga 3,690,000 Cfgpd/2
 hrs, Ga 2,930,000 Cfgpd/1 hr, Ga 2,530,000 Cfgpd/2 hrs, 300A, §
 dn, Ga 1,790,000 Cfgpd/6 hrs, Ga 1,932,000 Cfgpd & 1/2 to 3/4
 BWOH thru 2" tbg, Ga 1,630,000 Cfgpd & 3/4 BWP/3 hrs, Temp Plg
 @3090, Pf 16/3061-65 (CG), SI/12 hrs, Ga 500,000 Cfgpd/2 hrs -
 nat, 1000 Reg A, Ga 6,640,000 Cfgpd & 1 BAWPH/9 hrs, CO plf @
 3090, CO est 3150 PBD, 4 Pt Ind OF 10,000,000 Cfgpd, CG pfs 3061-
3113 - COMPLETED (12-16-64)

CSO EL Log

Win 2716 +314

CGro 2954 - 552