

A-6-85

2524 DF

MAP NO. _____

ELEV. 2516 GL

STATE Kansas COUNTY Meade SEC. 29Twp 34 S Rge 29 WOPERATOR Thomas & Brewer - Liberal, KansasLOC. SE NW *WELL NO. 1-29 FARM NAME H. G. Adams


FT. FROM _____ LINE

WELL Adams Ranch, Ext (PD 6100)

FT. FROM _____ LINE

FR. 11-16-60 SPUD 11-10-60 COMP. 5-31-61CONT./GEOL. Bennett & Roberts tools

NAME PRODUCING INTERVAL		COMPLETION RECORD		TREATMENT RECORD
FROM	TO	PERF. W/HOLES		
<u>Morrow</u>	<u>5841-5906</u>	<u>44</u>		<u>2500A-F/20X20</u>
<u>b</u>				
<u>c</u>				
<u>d</u>				

a I. P. OIL/DIST. _____ WTR. COF GAS 537 M.C.F.P.D. _____ CHK. 1 pt HRS. _____

b " " " " " " " " " "

c " " " " " " " " " "

d _____

D & A ()

SIP# 1761 FI TP # _____ FI CP# _____ SIBHP _____GOR. _____ GR. _____ PBDT 5938 TD 6075

CASING - CEMENT RECORD		Casing - Cement Record	
SIZE	DEPTH	W/SAX.	SIZE
<u>8-5/8"</u>	<u>1361</u>	<u>650</u>	
<u>4 1/2"</u>	<u>5970</u>	<u>100</u>	

OPERATOR Thomas & Brewer WELL NO. 1-29 H. G. Adams ELEV. 2524 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Toronto	4480	
			Lansing-Kansas City	4561	
			Marmaton	5300	
			Morrow	5814	
			Morrow Sand (broken)	5835-5918	
			Chester	5964	

* Correct location fr SE NW NW to C SE NW

Spud 11-10-60. 8-5/8" @ 1361 w/650 sx.

RTD 6075, Elogs.

DST # 1 (Morr & Chest) 5796-5969 (SP), op 1 hr, gd blo. 35 mins/
died, rec 165' GCM, FP 44-111, SIP 511/30 mins.

4 1/2" @ 5970 w/100 sx. MICT. CO to 5938.

P/8/Morr/5841-43, 4/5850-51, 8/5863-65, 12/5874-77, 8/5886-88,
4/5905-06. Rec wtr (communication). SQ 5841-5906 w/250 sx.
Re-SQ 5841-5906 w/100 sx. CO to 5938.Re-P/8/Morr/5841-43, 4/5850-51, 8/5863-65, 12/5874-77, 8/5886-88
4/5905-06. SSG-TSTM. 2500 Ac. Rec/SSG-TSTM. Frac 20,000
Ac X 20,000 sd. Rec 1d, ga 350 MCF. 24 hr BD 537 MCF. 24
hr SIP 1761.

IP 1 pt COF 537 MCF, 24 hr SIP 1761 from Morrow (5841-5906).

COMPLETE 5-31-61

LIBERAL TOPS

2525

Heebner 4429 (-1904)

Lansing 4562 (-2037)

Marmaton 5250 (-2725)

Morrow 5812 (-3287) T 178' ϕ 537 MCF

Miss 5990 (-3465)

TD 6081