


MAP NO. 59
STATE Kansas COUNTY Meade SEC. 23 TWP. 34S RGE. 29W
OPERATOR Texaco, Inc. LOC. C NW/4
WELL NO. 1 FARM NAME Adams "F" 1100 FT. FROM N LINE
DL Horace South FT. FROM _____ LINE

FR. 6/15/60 SPUD 6/12/60 COMP. 7/7/60

CONT./GEOL. Stickle Drlg. Tools

COMPLETION RECORD			
NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a <u>Co. Gr</u>	<u>3194-98</u>	<u>16</u>	<u>5000 Ac</u>
b _____	_____	_____	_____
c _____	_____	_____	_____
d _____	_____	_____	_____



COF
d I. P. OIL/DIST. _____ WTR. _____ GAS 27,534 M.C.F.P.D. _____ CHK. _____ HRS. _____
b " " " " " "
c " " " " " "
d _____

D & A ()

SIP#	FI TP #	FI CP#	SIBHP		
<u>871</u>	_____	_____	_____		
GOR. _____	GR. _____	PBTD <u>4350</u>	TD <u>4450</u>		
CASING - CEMENT RECORD					
SIZE	DEPTH	W/SAX.	SIZE	DEPTH	W/SAX.
<u>13</u>	<u>35</u>	_____	<u>4</u>	<u>4445</u>	_____
<u>8</u>	<u>434</u>	<u>300</u>	_____	_____	_____

OPERATOR Texaco, Inc. WELL NO. 1 Adams "F" ELEV. 2435 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Werf	2890	_____	_____	_____	_____
Co Gr	2942 <u>+507</u>	_____	_____	_____	_____
Co Gr pay	3190	_____	_____	_____	_____
Tor	4377	_____	_____	_____	_____
Ø 3196-3220, 23", 4" 1m, soft chalky, good poro, bldg gas, 2" dnse 1m, ns, 4" 1m soft fr poro bld gas, 5" 1m, bld gas, 8" 1m ns.					
Ø 4370-94, 19", all 1m, s/g.					
DST 4375-94, 65 min, gas 25 min, 15 MCFG, 185" gcm, 95" gc mw, FP 50-110#, BHP 1385-1265#/45.					
RTD 4450. CO 4350. 16/3194-98. Ac 5000. 5,690 MCF/14 hr csg.					

LIBERAL ELECTRIC LOG TOPS

2438 KB

Winfield 2645 (-207)

Council Grove 2876 (-438) g 27.534 MCF ¢

Heebner 4338 (-1900)

Toronto 4368 (-1930) tst 15 MCF, 185' GCM, 95' GCMW

TD 4450