


MAP NO. _____ A-4-4 ELEV. 2510 DF
 STATE Kansas COUNTY Meade SEC. 16 Twp 34 S Rge 29 W
 OPERATOR Thomas & Brewer LOC. C NE SW
 WELL NO. 1-16 FARM NAME Adams FT. FROM _____ LINE _____
 JOE Horace FT. FROM _____ LINE _____
 FR. 1-27-61 SPUD 1-20-61 COMP. 3-15-61

CONT./GEOL. _____
 NAME PRODUCING INTERVAL COMPLETION RECORD TREATMENT RECORD
 FROM - TO PERF. W/HOLES
 a Morrow 5808-14 24 2000A-AcF 20X20



d I. P. OIL/DIST. WTR COF GAS 5,380 M.C.F.P.D. CHK. 4 pt HRS. _____
 b " " " " " "
 c " " " " " "
 d _____

SITP 1250 SICP 1380

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. _____ PBDT 5830 TD 6051
 CASING - CEMENT RECORD
 SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.
 8-5/8" 375 600
 4 1/2" 5890 125

OPERATOR Thomas & Brewer WELL NO. 1-16 Adams ELEV. 2510 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Morrow				5769	
Morrow Sand				5805-49	
Chester				5870	

Spud 1-20-61. 8-5/8" @ 375 w/600 sx.

DST # 1 (Morr & Chest) 5761-5881, op 1 hr, GTS 3 mins, ga 1020
 MCF/60 mins, rec 18' GCM, pkr fld, FP 490-575, SIP 2065/30
 mins, HSH 3295-3060.

RTD 6051, Elogs. 4 1/2" @ 5890 w/125 sx. MICT. CO to 5830.

P/24/5808-14. 2000 Ac. Frac 20,000 Ac X 20,000 sd. Ga 8,500
 MCF + 1d. SIP 1575. Rec 1d.

IP 4 pt COF 5,380 MCF, SITP 1250, SICP 1380 from Morrow
 (5808-14).

COMPLETE 3-15-61

5769
 2512
 -3257

LIBERAL TOPS

611456

2512 KB

Heebner 4394 (-1882)

Lansing 4522 (-2010)

Morrow 5770 (-3258) T 100', Tss 44'

"S-2" 5805 (-3293) 44/44, 8.5 M after frac.

Chester 5870 (-3358)

TD 6074

Mim 5214 = 3002

4550-2038