


State KS Field MOHLER EXT.
 Company SKELLY County MEADE
 Farm D. J. KOLB No. 1
 Sec. 3 Twp. 34 Range 29

Spot NE NE NW
 Contractor HUME
 Remarks 6000' MISS



Comm. 11-20-57 Comp. 1-27-58
 Elev. DF 2515.02 GL 2507 KB 2517 TD 5724 PB 5796
 Pay MOR 5777-84

1 1/2 M FLO } 28.480 + GRAV. 38°
I.P. 9.9% } 1,160 M.S.F. S.I.P. 1575.
 Casing Record: 13 3/8 7"
20" 10 3/4 5 1/2" 5720/250
16" 8 5/8 1495/900

WORT	Sample	Log
NOV 1 3 ✓	Heeb 4410	Heeb 4412
NOV 2 0 RURT	LANS 4574	LANS 4579
NOV 2 7 TD 1495 min	MARM 5220	MARM 5216
CG 8 5/8	" PAY 5287	" PAY 5288
DEC 1 4 8 3/8	CHER 5445	CHER 5445
Ø 31.35	MOR 5742	MOR 5740
DEC 1 1 Ø 4540	" sd 5770	" sd 5767
DEC 1 8 DST 5211-40	CHESTER 5824	" " 5778-8
op lhr. rec 30' SM ± G		" " 5792-58
CSW + oil sho +		CHESTER 582
90' M ± G CSW + 500' G CSW		
FP 59-283 BHP 1683/20"		
DST 5282-92 op lhr.		
rec 450' G in DP + 130'		
G ± 0 CM + 150' G CSW		
FP 59-170 BHP 1409/60"		

~~★~~
 JAN 1 5770-84 gas kick of 125 unit
 DST 5730-84 op lhr. GTS 2 1/2 min
 g 1350 MCF/5" g 2190 MCF/5 g 2365 MCF/10
 rec 40' G CM + 360' G 8 VHO CM + 50' oil FP 225
 BHP 1880/20" ~~TD 5826~~
 DST 5784-5826 op lhr. GTS 15" g 76 MCF

611485

FP 45-150 BHP 1860/20"

~~DST~~ ATP 5924 ran log

DST 5863-5924 of 1hr see 35'M

FP 20-20 BHP 45/20" 5 1/2" 1000

JAN 8 RUCT

JAN 15 MICT CO 5841 G/R pt 8/5801-03

swab 50 gal SWPH + 550 Sq/200

CO 5841 36/5794-5800 swab 1/2 gal WPH

for 4 hr. up 8/5794-5800 MA/250 swab

18 BW + oil sho for 10 1/2 hr Sq/100

JAN 22 Co 5796 pt 39/5777-84 g 280 MCF

+ cond sho. pt 18/5769-72 1 hr BD

g 1,560 MCF + 30 gal cond PH 51 3 hr

SICP 350 FR/4000 3 1/2/4000 8 hr BD

g 2,060 MCF + cond FCP 320 18 hr


SICP 1700 4 hr BD g 2,060 MCF + oil sh

FCP 410 ~~SI~~ MOCT ~~SI~~

JAN 29 SICP 1575 SITP 1200

14 1/2 hr flo g 1,160 MCF + 28.4 BO

FCP 840 ATP 600 GRAV. 38°



AMARILLO TOPS

2517 KB

Heebner 4415 (-1898)

Lansing 4579 (-2062)

Morrow 5740 (-3223) T 83', 35' Tss

"S-2" Sd 5768 (-3251) T 35' brkn, 28' por, G 28.4 BO +
1,160 MCF

Miss 5823 (-3306) NS

TD 5924 (-3047)