


15-34s-30w

RELEASED
FROM
CONFIDENTIAL



TRILOBITE
TESTING, INC.

RECEIVED
OCT 29 2003
KCC WICHITA

DRILL STEM TEST REPORT

Prepared For: Raydon Exploration

CONFIDENTIAL

9400 W. Broadway Ste. 400 Oklahoma City
OK 7311

ORIGINAL KCC

ATTN: Ed Grieves

OCT 28 2003

15-34S-30W Meade KS

CONFIDENTIAL

Cimarron 2-15

Start Date: 2003.09.17 @ 11:15:04

End Date: 2003.09.17 @ 21:01:40

Job Ticket #: 16140

DST #: 1

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620

Raydon Exploration

Cimarron 2-15

15-34S-30W Meade KS

DST # 1

Council Grove A

2003.09.17

 TRILOBITE TESTING, INC.	DRILL STEM TEST REPORT	
	Raydon Exploration	Cimarron 2-15
	9400 N. Broadway Ste. 400 Oklahoma City OK 7311	15-34S-30W Meade KS
	ATTN: Ed Grieves	Job Ticket: 16140 DST#: 1 Test Start: 2003.09.17 @ 11:15:04

GENERAL INFORMATION:

Formation: **Council Grove A**
 Deviated: No Whipstock: ft (KB)
 Time Tool Opened: 13:37:21
 Time Test Ended: 21:01:40

KCC**OCT 28 2003****CONFIDENTIAL**


Test Type: Conventional Bottom Hole
 Tester: Chris Hagman
 Unit No: 17

Interval: **3179.00 ft (KB) To 3192.00 ft (KB) (TVD)**
 Total Depth: 3192.00 ft (KB) (TVD)
 Hole Diameter: 7.78 inches Hole Condition: Good

Reference Elevations: 2688.00 ft (KB)
 2678.00 ft (CF)
 KB to GR/CF: 10.00 ft

Serial #: 6771 Inside
 Press@RunDepth: 79.39 psig @ 3182.00 ft (KB) Capacity: 7000.00 psig
 Start Date: 2003.09.17 End Date: 2003.09.17 Last Calib.: 1899.12.30
 Start Time: 11:15:09 End Time: 21:01:41 Time On Btm: 2003.09.17 @ 13:36:11
 Time Off Btm: 2003.09.17 @ 18:09:51

TEST COMMENT: IF: Strong blow BOB 30 sec. GTS 15 min.
 IS: No blow back
 FF: Strong blow BOB 30 sec. GTS 30 sec.
 FS: No blow back

**PRESSURE SUMMARY**

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1576.12	92.56	Initial Hydro-static
2	21.69	92.45	Open To Flow (1)
33	70.56	92.56	Shut-In (1)
97	775.77	92.81	End Shut-In (1)
98	68.78	92.73	Open To Flow (2)
155	79.39	91.73	Shut-In (2)
273	767.16	90.21	End Shut-In (2)
274	1512.26	90.29	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
124.00	Muddy Water: 85% m, 15% w	0.61

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
First Gas Rate	0.25	10.00	38.71
Last Gas Rate	0.38	29.00	158.98
Max. Gas Rate	0.38	29.00	158.98

CONFIDENTIAL

ORIGINAL


**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

TOOL DIAGRAM

Raydon Exploration

Cimarron 2-15

9400 N. Broadway Ste. 400 Oklahoma City OK
7311

15-34S-30W Meade KS

Job Ticket: 16140

DST#: 1

ATTN: Ed Grieves

Test Start: 2003.09.17 @ 11:15:04

Tool Information

Drill Pipe:	Length: 2888.00 ft	Diameter: 3.80 inches	Volume: 40.51 bbl	Tool Weight: 2000.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 30000.00 lb
Drill Collar:	Length: 271.00 ft	Diameter: 2.25 inches	Volume: 1.33 bbl	Weight to Pull Loose: 95000.00 lb
		Total Volume:	41.84 bbl	Tool Chased 0.00 ft
Drill Pipe Above KB:	8.00 ft			String Weight: Initial 64000.00 lb
Depth to Top Packer:	3179.00 ft			Final 64000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	13.00 ft			
Tool Length:	41.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		
Tool Comments:				

KCC

OCT 28 2003

CONFIDENTIAL

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			3152.00	
Shut In Tool	5.00			3157.00	
Hydraulic tool	5.00			3162.00	
Jars	5.00			3167.00	
Safety Joint	2.00			3169.00	
Change Over Sub	1.00			3170.00	
Packer	5.00			3175.00	28.00 Bottom Of Top Packer
Packer	4.00			3179.00	
Stubb	1.00			3180.00	
Perforations	2.00			3182.00	
Recorder	0.00	6771	Inside	3182.00	
Perforations	7.00			3189.00	
Recorder	0.00	13761	Inside	3189.00	
Bullnose	3.00			3192.00	13.00 Bottom Packers & Anchor

Total Tool Length: 41.00



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Raydon Exploration

Cimarron 2-15

9400 N. Broadway Ste. 400 Oklahoma City OK
7311

15-34S-30W Meade KS

Job Ticket: 16140

DST#: 1

ATTN: Ed Grieves

Test Start: 2003.09.17 @ 11:15:04

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

48000 ppm

Viscosity: 44.00 sec/qt

Cushion Volume:

bbl

Water Loss: 10.35 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 12400.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
124.00	Muddy Water: 85% _m , 15% _w	0.610

Total Length: 124.00 ft

Total Volume: 0.610 bbl

Num Fluid Samples: 0


Num Gas Bombs: 1


Serial #:

Laboratory Name: Caraway

Laboratory Location: Liberal, KS

Recovery Comments: .126 RW @ 88 F





RECEIVED
OCT 29 2003
KCC WICHITA

DRILL STEM TEST REPORT

Prepared For: **Raydon Exploration**

9400 N. Broadway Ste. 400 Oklahoma City
OK 7311

ATTN: Ed Grieves

15-34S-30W Meade KS

Cimarron 2-15

Start Date: 2003.09.18 @ 12:23:50

End Date: 2003.09.18 @ 22:03:56

Job Ticket #: 16141

DST #: 2

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

Raydon Exploration

Cimarron 2-15

9400 N. Broadway Ste. 400 Oklahoma City OK
7311

15-34S-30W Meade KS

Job Ticket: 16141

DST#: 2

ATTN: Ed Grieves

Test Start: 2003.09.18 @ 12:23:50

GENERAL INFORMATION:

Formation: Council Grove "C"

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 14:31:07

Time Test Ended: 22:03:56

Test Type: Conventional Bottom Hole

Tester: Chris Hagman

Unit No: 17

Interval: 3216.00 ft (KB) To 3240.00 ft (KB) (TVD)

Total Depth: 3240.00 ft (KB) (TVD)

Hole Diameter: 7.78 inches Hole Condition: Good

Reference Elevations: 2688.00 ft (KB)

2678.00 ft (CF)

KB to GR/CF: 10.00 ft

Serial #: 6771

Inside

Press@RunDepth: 119.77 psig @ 3219.00 ft (KB)

Start Date: 2003.09.18

End Date: 2003.09.18

Start Time: 12:23:55

End Time: 22:03:57

Capacity: 7000.00 psig

Last Calib.: 1899.12.30

Time On Btm: 2003.09.18 @ 14:29:57


Time Off Btm: 2003.09.18 @ 19:06:57

TEST COMMENT: IF: Weak blow BOB 27 min.

IS: No blow back

FF: Weak blow 8 in. 60 min.

FS: No blow back



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1669.98	88.44	Initial Hydro-static
2	33.08	88.58	Open To Flow (1)
31	70.46	89.81	Shut-In (1)
95	684.97	90.31	End Shut-In (1)
96	76.36	90.29	Open To Flow (2)
152	119.77	91.70	Shut-In (2)
276	696.99	91.92	End Shut-In (2)
277	1515.60	91.07	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
186.00	Mud 50%, Water 50%	0.91
124.00	Mud 95%, Water 5%	0.95

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

Raydon Exploration

Cimarron 2-15

9400 N. Broadway Ste. 400 Oklahoma City OK
7311

15-34S-30W Meade KS

Job Ticket: 16141

DST#: 2

ATTN: Ed Grieves

Test Start: 2003.09.18 @ 12:23:50

Tool Information

Drill Pipe:	Length: 2941.00 ft	Diameter: 3.80 inches	Volume: 41.25 bbl	Tool Weight: 2000.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 30000.00 lb
Drill Collar:	Length: 273.00 ft	Diameter: 2.25 inches	Volume: 1.34 bbl	Weight to Pull Loose: 100000.0 lb
		Total Volume: 42.59 bbl		Tool Chased 0.00 ft
Drill Pipe Above KB:	26.00 ft			String Weight: Initial 65000.00 lb
Depth to Top Packer:	3216.00 ft			Final 66000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	24.00 ft			
Tool Length:	52.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
------------------	-------------	------------	----------	------------	----------------

Change Over Sub	1.00			3189.00	
Shut In Tool	5.00			3194.00	
Hydraulic tool	5.00			3199.00	
Jars	5.00			3204.00	
Safety Joint	2.00			3206.00	
Change Over Sub	1.00			3207.00	
Packer	5.00			3212.00	28.00 Bottom Of Top Packer
Packer	4.00			3216.00	
Stubb	1.00			3217.00	
Perforations	2.00			3219.00	
Recorder	0.00	6771	Inside	3219.00	
Perforations	18.00			3237.00	
Recorder	0.00	13761	Inside	3237.00	
Bullnose	3.00			3240.00	24.00 Bottom Packers & Anchor

Total Tool Length: 52.00



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

FLUID SUMMARY

Raydon Exploration

Cimarron 2-15

9400 N. Broadway Ste. 400 Oklahoma City OK
7311

15-34S-30W Meade KS

Job Ticket: 16141

DST#: 2

ATTN: Ed Grieves

Test Start: 2003.09.18 @ 12:23:50

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

105000 ppm

Viscosity: 43.00 sec/qt

Cushion Volume:

bbl

Water Loss: 9.98 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 10400.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
186.00	Mud 50%, Water 50%	0.915
124.00	Mud 95%, Water 5%	0.947

Total Length: 310.00 ft

Total Volume: 1.862 bbl

Num Fluid Samples: 0


Num Gas Bombs: 0


Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments: .083 RW @ 64 F





TRILOBITE
TESTING, INC.

RECEIVED
OCT 29 2003
KCC WICHITA

DRILL STEM TEST REPORT

Prepared For: **Raydon Exploration**

9400 N. Broadway Ste. 400 Oklahoma City
OK 7311

ATTN: Ed Grieves

15-34S-30W Meade KS

Cimarron 2-15

Start Date: 2003.09.26 @ 18:01:09

End Date: 2003.09.27 @ 04:58:24

Job Ticket #: 16115

DST #: 3

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620

Raydon Exploration


Cimarron 2-15

15-34S-30W Meade KS

DST # 3

Morrow sdst

2003.09.26



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

Raydon Exploration

Cimarron 2-15

9400 N. Broadway Ste. 400 Oklahoma City OK
7311

15-34S-30W Meade KS

ATTN: Ed Grieves

Job Ticket: 16115

DST#: 3

Test Start: 2003.09.26 @ 18:01:09

GENERAL INFORMATION:

Formation: **Morrow sdst**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 21:09:39

Time Test Ended: 04:58:24

Test Type: Conventional Bottom Hole

Tester: Blake Wallace

Unit No: 20

Interval: **5909.00 ft (KB) To 5940.00 ft (KB) (TVD)**

Reference Elevations: 2688.00 ft (KB)

Total Depth: 5940.00 ft (KB) (TVD)

2678.00 ft (CF)

Hole Diameter: 7.78 inches Hole Condition: Good

KB to GR/CF: 10.00 ft

Serial #: 3030

Inside

Press@RunDepth: 30.69 psig @ 5911.00 ft (KB)

Capacity: 7000.00 psig

Start Date: 2003.09.26

End Date:

2003.09.27

Last Calib.: 1899.12.30

Start Time: 18:01:13

End Time:

04:58:24

Time On Btmr: 2003.09.26 @ 21:07:39


Time Off Btmr: 2003.09.27 @ 01:40:24

TEST COMMENT: IF-weak blow built to 1 inch

IS-no blow back

FF-weak surface blow for 45 sec waited 20 min flushed tool with same results

FS-no blow back



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2927.35	120.74	Initial Hydro-static
2	18.59	120.96	Open To Flow (1)
30	23.94	121.83	Shut-in(1)
93	41.74	123.77	End Shut-in(1)
93	20.01	123.79	Open To Flow (2)
144	30.69	125.08	Shut-in(2)
272	50.81	127.59	End Shut-in(2)
273	2792.34	127.62	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
30.00	100% mud	0.15

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

TOOL DIAGRAM

Raydon Exploration

Cimarron 2-15

9400 N. Broadway Ste. 400 Oklahoma City OK
7311

15-34S-30W Meade KS

Job Ticket: 16115

DST#: 3

ATTN: Ed Grieves

Test Start: 2003.09.26 @ 18:01:09

Tool Information

Drill Pipe: Length: 5627.00 ft Diameter: 3.80 inches Volume: 78.93 bbl
Heavy Wt. Pipe: Length: 0.00 ft Diameter: 0.00 inches Volume: 0.00 bbl
Drill Collar: Length: 272.00 ft Diameter: 2.25 inches Volume: 1.34 bbl
Total Volume: 80.27 bbl

Tool Weight: 1800.00 lb

Weight set on Packer: 20000.00 lb

Weight to Pull Loose: 108000.0 lb

Tool Chased 0.00 ft

String Weight: Initial 80000.00 lb

Final 82000.00 lb

Drill Pipe Above KB: 17.00 ft

Depth to Top Packer: 5909.00 ft

Depth to Bottom Packer: ft

Interval between Packers: 31.00 ft

Tool Length: 58.00 ft

Number of Packers: 2 Diameter: 6.75 inches

Tool Comments:

Tool Description

Length (ft) Serial No. Position Depth (ft) Accum. Lengths

Shut In Tool	5.00			5887.00	
Hydraulic tool	5.00			5892.00	
Jars	5.00			5897.00	
Safety Joint	3.00			5900.00	
Packer	5.00			5905.00	27.00 Bottom Of Top Packer
Packer	4.00			5909.00	
Stubb	1.00			5910.00	
Perforations	1.00			5911.00	
Recorder	0.00	3030	Inside	5911.00	
Perforations	26.00			5937.00	
Recorder	0.00			5937.00	
Bullnose	3.00			5940.00	31.00 Bottom Packers & Anchor

Total Tool Length: 58.00



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Raydon Exploration

Cimarron 2-15

9400 N. Broadway Ste. 400 Oklahoma City OK
7311

15-34S-30W Meade KS

Job Ticket: 16115

DST#: 3

ATTN: Ed Grieves

Test Start: 2003.09.26 @ 18:01:09

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 44.00 sec/qt

Cushion Volume:

bbl

Water Loss: 6.39 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 2800.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
30.00	100% mud	0.148

Total Length: 30.00 ft

Total Volume: 0.148 bbl

Num Fluid Samples: 0


Num Gas Bombs: 0


Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:





RECEIVED
OCT 29 2003
KCC WICHITA

DRILL STEM TEST REPORT

Prepared For: **Raydon Exploration**

9400 N. Broadway Ste. 400 Oklahoma City
OK 7311

ATTN: Ed Grieves

15-34S-30W Meade KS

Cimarron 2-15

Start Date: 2003.09.28 @ 03:44:04

End Date: 2003.09.28 @ 13:55:19

Job Ticket #: 16116 DST #: 4

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620

Raydon Exploration

Cimarron 2-15

15-34S-30W Meade KS

DST # 4

Chester

2003.09.28



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

Raydon Exploration

Cimarron 2-15

9400 N. Broadway Ste. 400 Oklahoma City OK
7311

15-34S-30W Meade KS

Job Ticket: 16116

DST#: 4

ATTN: Ed Grieves

Test Start: 2003.09.28 @ 03:44:04

GENERAL INFORMATION:

Formation: **Chester**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 06:49:49

Time Test Ended: 13:55:19

Test Type: Conventional Bottom Hole

Tester: Blake Wallace

Unit No: 20

Interval: **5952.00 ft (KB) To 6010.00 ft (KB) (TVD)**

Reference Elevations: 2688.00 ft (KB)

Total Depth: 6010.00 ft (KB) (TVD)

2678.00 ft (CF)

Hole Diameter: 7.78 inches Hole Condition: Good

KB to GR/CF: 10.00 ft

Serial #: 3030

Inside

Press@RunDepth: 32.11 psig @ 5954.00 ft (KB)

Capacity: 7000.00 psig

Start Date: 2003.09.28

End Date:

2003.09.28

Last Calib.: 1899.12.30

Start Time: 03:44:08


End Time:

13:55:19

Time On Btm: 2003.09.28 @ 06:47:04

Time Off Btm: 2003.09.28 @ 11:30:04

TEST COMMENT: F-weak blow built to 3 inches
IS-no blow back
FF-weak blow died in 1 min
FS-no blow back



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2977.25	116.83	Initial Hydro-static
3	24.36	116.77	Open To Flow (1)
34	30.61	119.91	Shut-In(1)
96	79.39	122.63	End Shut-In(1)
98	28.30	122.66	Open To Flow (2)
152	32.11	124.40	Shut-In(2)
282	137.85	127.24	End Shut-In(2)
283	2934.62	127.40	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
40.00	5% G 95% M	0.20

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



**TRILOBITE
TESTING, INC.**

DRILL STEM TEST REPORT

TOOL DIAGRAM

Raydon Exploration

Cimarron 2-15

9400 N. Broadway Ste. 400 Oklahoma City OK
7311

15-34S-30W Meade KS

Job Ticket: 16116

DST#: 4

ATTN: Ed Grieves

Test Start: 2003.09.28 @ 03:44:04

Tool Information

Drill Pipe:	Length: 5701.00 ft	Diameter: 3.80 inches	Volume: 79.97 bbl	Tool Weight: 1800.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 20000.00 lb
Drill Collar:	Length: 241.00 ft	Diameter: 2.25 inches	Volume: 1.19 bbl	Weight to Pull Loose: 100000.0 lb
		Total Volume:	81.16 bbl	Tool Chased 0.00 ft
Drill Pipe Above KB:	17.00 ft			String Weight: Initial 82000.00 lb
Depth to Top Packer:	5952.00 ft			Final 84000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	58.00 ft			
Tool Length:	85.00 ft			
Number of Packers:	2	Diameter:	6.75 inches	

Tool Comments:

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Shut In Tool	5.00			5930.00	
Hydraulic tool	5.00			5935.00	
Jars	5.00			5940.00	
Safety Joint	3.00			5943.00	
Packer	5.00			5948.00	27.00 Bottom Of Top Packer
Packer	4.00			5952.00	
Stubb	1.00			5953.00	
Perforations	1.00			5954.00	
Recorder	0.00	3030	Inside	5954.00	
Perforations	10.00			5964.00	
Change Over Sub	1.00			5965.00	
Blank Spacing	31.00			5996.00	
Change Over Sub	1.00			5997.00	
Perforations	10.00			6007.00	
Recorder	0.00	11019		6007.00	
Bullnose	3.00			6010.00	58.00 Bottom Packers & Anchor
Total Tool Length:	85.00				



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

Raydon Exploration

Cimarron 2-15

9400 N. Broadway Ste. 400 Oklahoma City OK
7311

15-34S-30W Meade KS

Job Ticket: 16116

DST#: 4

ATTN: Ed Grieves

Test Start: 2003.09.28 @ 03:44:04

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 50.00 sec/qt

Cushion Volume:

bbl

Water Loss: 5.60 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 2500.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
40.00	5% G 95% M	0.197

Total Length: 40.00 ft

Total Volume: 0.197 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

