

DIAGRAMMATIC SKETCH
FINAL COMPLETION

HORIZON OIL & GAS CO. AND EDWIN L. COX "ADAMS #1-32"

Kansas City Production

Upper Morrow Production

Lansing Production
G.L. Elevation 2623'

New
8-5/8" Casing @ 1475'
24#

Top of cement @ 3820'

T. Lansing ~~Sand~~ @ *4520*
4514'

Lansing Perfs @ 4540-45-
41-45-43

1 1/2" tubing @ 4585'
1.9#

1 1/2" tubing @ 4782
Model J-Double-Grip-Snap-on
Packer @ 4789'

Kansas City Perfs. @ 4832

Model "D" Packer @ 5700'

1 1/2" tubing @ 5700'

Upper Morrow Perfs @ 5826,
5827'

5 1/2" casing @ 6,000'
15.5#

TOTAL DEPTH 6510'

B. Lansing
T. Kansas City ~~Sand~~ @ 4800'

B. K.C.

T. Upper Morrow ~~Sand~~ 5784'

B. MW 5888