

NENE 2700
NENW 2685
S 2 ME 2690

Correction.

4

State Kansas Field _____
County Meade
Company Columbian Fuel
Farm De Moss Well No. # 1
Sec. 3 Twp. 34 S Range 30 W
fr N fr E fr S fr W
of De Moss C NENE

Contractor _____
Remarks _____
Comm. 7-3-55 Comp. 10-5-55
Elev. 2700 T. D. 5385 P. B. _____
Pay 5290-96
Gr. 41°

I. P. 5980 PD R. P. _____
Casing Record: 13 3/8 723/500 7
20 10 3/4 _____ 5 1/2 5380/400
16 85/8 2707/800

	Tops
	<u>DST 1042-75 open 8" gd sample</u>
	<u>ble downed to wh. in Navy pay 5296</u>
	<u>570' hr SWCM. FP 360</u>
	<u>BH 360/20</u>
	<u>5285-96 in 11'</u>
7 1/2'	ls tite
2'	sh
1'3"	ls tite
3"	sh
	<u>5296-5342 in 46'</u>
46'	hs tan to buff olivaceous
	gd to fr. por. bleed O&G sat.
	patches sw in top 33' gd flow in
	top 20' TTD 5342
	<u>DST 5297-5312 (sp) open 2 1/2 hrs</u>
	<u>g in 2 hrs g 84 wcf oil in</u>
	<u>2 hrs 9 min wcf. 2 BOPH in</u>
	<u>180' m. gassy oil 4570' fluid oil</u>
	<u>FP 150-1125 BH 1500/20</u>

5342-64 m 22'
12' ls oolitic gl por ss.
8½' ls gry to dk gry tite
1½ sh dk gry

RTD 5385 run schel top

RUCT CO to 5347 / Novinger pay 5290
Pg 36/5290-96

2½" tub w phat 5223 run rods
POP. pumped load. pumped 32.4

BO + 11 B SW no time

pumped 65 BO + 16 B SW in 24hrs

" " 59 BO + 16 B SW in 24hrs

GOR 500:1 gravity 41°

CP = 75# State Test.

hold For Tape

OCT 5 1955

Schlee by Co.

Cim 1465

Stone Coral 1668

Zwell 2144

Holding 2634

Herr 2694

Kri 2763

Winf. 2820

WTR 2878

L 15TR 2958

Florence 3004

Lana 4595

Martin 5229

Novinger pay 5290-5349

4