

Company- THE TEXAS COMPANY
Farm- G. M. Gruber No. 1
O/A

SEC. 12 T. 34 R. 31W
C 17/4
1320' fr N & E Lines of NE/4
12-34-31W
County Seward
KANSAS

Total Depth. 6029'
Comm. 12-12-57 Comp. 1-14-58
Shot or Treated.
Contractor. Noble Drig. Co.
Issued. 6-7-58

CASING:
13 3/8" 597' cem w/600 sx.
8 5/8" 2690' cem w/300 sx.
5 1/2" 6026' cem w/250 sx.

Elevation. 2713' DF

Production. 240,000 MCF

Figures Indicate Bottom of Formations.

shale & sand	675
shale, sand, red beds	2099
shale, lime, red beds	2345
shale & lime	2843
sand	2846
shale & sand	2930
shale & lime	3009
shale, sand & lime	3084
shale & lime	3322
shale, sand & lime	3462
shale & lime	3992
shale	4072
shale & lime	4529
shale, lime, broken	
chert	4549
shale & lime	4832
lime	4901
shale, lime, broken chert	4947
no shown	4993
lime & shale	5277
shale & lime	5330
lime & shale	5371
shale & lime	5530
lime & shale	5537
shale & lime	5722
sand & shale	5737
no shown	5750
shale & lime	5803
lime, shale & sand	5825
lime & shale	5835
shale & lime	6025
shale	6026
shale	6029
Total Depth	

TOPS:

Anhydrite (scout)	1415
Herrington	2638
Neva (scout)	3165
Heebner	4352
Toronto	4395
Lansing	4516
Marmaton	5192
Cherokee	5386
Atoka	5568
Morrow	5713
Chester	5872
St. Genevieve	6014

Perf. 5792-5808 2-4-58