

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas 11-34-31W

Company- J. M. HUBER CORPORATION
 Farm- Iris No. 1

SEC. 11 T. 34 R. 31W
 C SE SW

Total Depth. 6030'
 Comm. 7-10-62 Comp. 8-4-62
 Shot or Treated.
 Contractor. McClellan Drilling
 Issued. 2-16-63

County Seward
 KANSAS



CASING:

8 5/8" 1555' cem w/900 sx.
 5 1/2" 6031' cem w/525 sx.

Elevation. 2628'

Production. 8,800,000 CFG

Figures Indicate Bottom of Formations.

surface clay	300
surface clay & sand	490
red bed & gyp	970
sand	985
red bed & gyp	1170
red bed, gyp & sand	1374
red bed & gyp	1556
shale & shells	1810
lime & shale	2907
lime	2935
lime & shale	3280
lime	3365
lime w/shale streaks	3495
lime & shale	3670
shale	3860
lime & shale	4422
lime	4485
lime & shale	4533
lime & shale	4967
lime	5285
lime & shale	5438
lime	5517
lime & shale	5751
lime	6030 RTD
Total Depth	

TOPS: SAMPLE

Wreford	2835
Council Grove	2976

TOPS: LOG

Base Heebner	4232
Toronto	4237
Lansing	4374
Drum	4662
Hodges	4852
Marmaton	5034
Cherokee	5195
Atoka	5501
Morrow	5542
Chester	5676
Chester Sand	5760
Ste. Genevieve	5790
St. Louis	5976