

3-143W  
MAP NO.

SEC. 6 TWP. 34S RGE. 31W

STATE Kans COUNTY Seward LOC. App C SW

OPERATOR Gulf Oil Corp. 1250 FT. FROM S LINE


WELL NO. 1 FARM NAME Robert Davies 1250 FT. FROM W LINE

Blue Bell, NW ELEV. 2542 GR 2550 DF 2551 KB

FR. 10/26/61 SPUD 10/24/61 COMP. 3/13/62

CONT. Wakefield Tools /GEOL. Bob Dreyer

NAME PRODUCING INTERVAL	COMPLETION RECORD		PERF. W/HOLES	TREATMENT RECORD
	FROM - TO			
<u>Morr</u>	<u>5714-24</u>		<u>20</u>	<u>Frac</u>
b				
c				
d	<u>Co Ga</u>			



a I. P. OIL/DIST. 9 B0 WTR. 0 GAS no Ga M.C.F.P.D. CHK. 18/64 HRS. 24

b " " " " " "

c " " " " " "

d

SIP# \_\_\_\_\_ FI TP # 60 FI CP# 205 SIBHP 1530 D & A ( )

WOR. \_\_\_\_\_ GR. Est 39 deg. PBDT 5866 TD 6133

CASING - CEMENT RECORD		CASING - CEMENT RECORD	
SIZE	DEPTH	SIZE	DEPTH
<u>20"</u>	<u>85</u>	<u>4 1/2"</u>	<u>5901</u>
<u>8 5/8"</u>	<u>1487</u>	<u>820</u>	<u>175</u>

OPERATOR Gulf Oil Corp. WELL NO. 1 Robert Davies ELEV. 2551 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB Tops & Datums			Kri	2452	+ 99
			Winf	2524	+ 27
RTD (St Gen) 6133		-3582	UFR	2590	- 39
			LFR	2640	- 89
			CG	2828	- 277
			Hb	4154	-1603
			Tor	4188	-1637
			Lans	4322	-1771
			Marm	5026	-2475
			Morr Sh	5562	-3011
			Morr sd	5714	-3163
			Ches	5778	-3227
			St Gen	6070	-3519

DST #1 (Morr) 5710-55, Op 2 hrs, GTS/5", Ga 280 Mcfgpd 15", Ga 362 Mcfgpd/30", Ga 486 Mcfgpd/45", Ga 584 Mcfgpd/60", Ga 648 Mcfgpd/75", Ga 1140 Mcfgpd/90", Ga 1140 Mcfgpd/105", & 120", R 175' HO & GCM, IBHP 1544#/30", IFP 22#, FFP 87#, FBHP 1813#/30".

3-143W  
SHEET NO. 2 MAP NO. \_\_\_\_\_  
STATE Kans COUNTY Seward SEC. 6 TWP. 34S RGE. 31W  
OPERATOR Gulf Oil Corp. Loc App C SW  
WELL NO. 1 FARM NAME Robert Davies

DST #2 (Ches) 5779-5801, Op 5", V Wk Blo, SI/30", Op ½ hrs, no blo, R 10<sup>1</sup>M, IBHP 95#/30", IFP 76#, FFP 76", FBHP 76#/30".

RTD 6133. Log. 4½" @ 5901 w/175 sx. CO 5866, GRN Log to 5500, 20/5714-24 (Morr) Frac (14,700# sd x 200 BA), Tbg to 5714, Swb 40 BO + 160 B ld/10 hrs, SITP 200#, SICP 1500#/12 hrs, Flo 60 BO + 67 B ld Gr 39 deg @ 74 deg/18 hrs, Gas Ga 517 Mcfgpd, FTP 310#, FCP 310#, SITP 650#, SICP 950#/2 hrs, Flo 39 BO/NW, 18/64" ck/24 hrs, FTP 145#, FCP 310#, GA 645 Mcfgpd, SITP 1185#, SICP 1185#/48 hrs, Flo 16 BO, 20/64", ck, 19 hrs, FTP 90#, FCP 310#, Ga 190 Mcfgpd, F 10 BO/NW, 18/64" ck/24 hrs, + Ga 110 Mcfgpd, FTP 60#, FCP 215#, Flo 13 BO/NW, 18/64" ck, 48 hrs, FTP 65#, FCP 340#, Ga 80 Mcfgpd, SITP 1260# SICP 1206#, Est over 72 hrs, Flo 33 BO/NW thru

OPERATOR Gulf Oil Corp.

WELL NO. 1 Robert Davies

18/64" ck, 69 hrs, Ga 90 Mcfgpd, FTP 100#, FCP 205#, Flo 9 BO/NW thru 18/64" ck/24 hrs, FTP 90#, FCP 200#, Ga 90 Mcfgpd, Flo 11 BO/NW thru 18/64" ck/24 hrs, FTP 90#, FCP 190#, Ga 70 Mcfgpd. Co Ga Flo 9 BOPD/NW, 18/64" ck, FTP 60#, FCP 205# Static BHP 1530#, IBHP 1813#, no GOR Avail. Morr 5714-24.

COMPLETED

LIBERAL ELECTRIC LOG TOPS

2551 KB

Winfield 2576 (-25)

Council Grove 2828 (-277)

Heebner 4170 (-1619)

Toronto 4192 (-1641)

Lansing 4322 (-1777)

Marmaton 5026 (-2475)

Morrow 5563 (-3012)

"S-3" 5714 (-3163) 10/19;  $\phi$  9 BO/24 hrs. (no water)

Chester 5765 (-3214)

Ste. Gen 6070 (-3519)

TD 6133