

4-281W

MAP NO.

84

SEC 6-34S-31W

STATE Kans.

COUNTY

Seward

LOC. 100' W of C SW NE

OPER Gulf Oil Corp., Wichita, Kansas

FT/FR

LINE

WELL #2 FARM Robert Davies

FT/FR

LINE

Arkalon, Ext.

ELEV 2519

GR. 2529

DF 2532

KB

CO. INT. Earl F. Wakefield Tools

GEOL.

6150' Miss test

FR. 2/28/64

SPUD

3/2/64

COMP.

4/28/64

TD 6159

FM

Ste Gen

PBTD

PRODUCING FM.

FROM

TO

PERF W/HOLES

TREATMENT

Morrow

5678 - 84

12

Frac

I.P. 4 Pt. IOF 22,900,000 Cfgpd (SIP 1583#)

Completion Record

Casing Record

8-5/8" @ 1488 w/650 sx.

4 1/2" @ 6078 1/2 w/125 sx.

Data Inc.

KB Log Tops:

Hb	4118	-1586	Mrw sh	5538	-3006	Ste Gen	6014	-3482
Lans	4302	-1770	Mrw lm	5614	-3082	LTD not available		
Marm	5006	-2474	Mrw sd	5670	-3138	RTD	6159	-3627
Cher	5154	-2622	Ches	5693	-3161			

Drill to 5223, hole off 7 deg, cem back to 4728, Drlg. ahead to

straighten hole, Drill pipe cemented in hole, set whipstock @ 4082, Drlg. new hole @ 5223, II

DST #1 (Mrw sd) 5857-5946 (Str Pkr) Op 1 hr., no blo, R 10' M, ISIP 726#/30", IFP 3#, FFP 23#, FSIP 384#/30"

RTD 6159, 4 1/2" @ 6078 1/2 w/125 sx., MICT, Pf (Mrw lm) 12/5678-84 Frac (17,000 gelled AW x 15,000# sd) Ga 2,830,000 Cfgpd + 1/2 B Cond PH/NT, Rec 12 B Cond/24 hrs (Grav. 61 deg. @ 54 deg)

4 pt Ind OF 22,900,000 Cfgpd, No flu, 72 hr. SIP 1581#, 1583# BHP @ 5660=1869#, Mrw 5678-84, COMPLETE (4/21/64)

LIBERAL ELECTRIC LOG TOPS

2532 KB

Winfield 2551 (-19)
Council Grove 2799 (-267)
Heebner 4142 (-1610)
Toronto 4163 (-1631)
Lansing 4300 (-1768)
Marmaton 4996 (-2464)
Morrow 5538 (-3006)
"S-3" 5665 (-3133) 22/25; IP 22.9-M-
Chester 5693 (-3161) DST/Mud
Ste. Gen 6012 (-3480)
St. Louis (?) 6101 (-3569)
TD 6161