

8-250W Map No. K-84

OPER GULF OIL CORPORATION

Wichita, Kansas

WELL #1 RICE DAVIES "A"


Rine Drilling

FIELD Arklon Field, Ext (Chest & Mrw)

P. OF; 4,250,000 CFGPD / SIBHP 1834 at 5780,
25 BOPD, Gr 56 deg, Mrw 5737-6058

No DST's, No Cores, RTD 6196, Ran Log, 4" @6170 w/150
sx.:

MICT, Pf 8/5804-08, 8/5832-36, 8/5906-10, 8/5968-
72, 8/6054-58 (Miss), Acid Frac (20,000 (15%) HCL x
10,000 (10%) Acetic) in 4 stages w/8 ball sealers in
last stage, Max P 3100#, Drop to 0#/2 hrs after SD,
8 & flo 42 BO & 3% LW & 300,000 Cfgpd thru 3/4" choke/
12 hrs, Blanking Plg @5791, Model "P" Pkr @5793, 4/
5737-39, 4/5755-57 (Mrw), Frac 22,300# sd x 950# RA
walnut hulls x 540 B (3%) AW, Max P 3700#, Min P 2800#,
On vac 2 1/2 hrs - Rec ld, Ga 1,450,000 Cfgpd & 10 BO &
68 BLW/18 hrs thru 20/64" choke, Ga 1,140,000 Cfgpd &
4 BO/9 hrs thru 14/64" choke, Ga 2,000,000 Cfgpd thru
tbg, Flo 19 BO & 8 BW & 1,450,000 Cfgpd/12 hrs thru
19/64" choke, SITP 900#, SICP 1200#, GOR 40,000:1
4 Pt Cal OF; 4,250,000 CFGPD / (SIBHP 1834 at 5780),
BOPD, Gr 56 deg, Mrw 5737-6058 - COMPLETED on 8-23-65



S-T-R 7-34S-31W

SPOT C SW NE ✓

CO SEWARD, Ks.

ELEV 2580 KB

(KB Log)

Hb 4186 -1606
Tor 4234 -1654
Lan 4358 -1778
Mar 5056 -2476
Mrw sh 5610 -3030
Mrw sd 5752 -3172
B/sd 5760 -3180
Chest 5772 -3192
Ste G 6098 -3518
LTD 6198 -3618

Data Inc

MISCEL DATA

GEOL Bob Creyer

FTG _____

SUPPT _____

CSG 8" @1495' w/700 Sx. 4" @6170' w/150 Sx.

L-S

ELEV 2577 DF SPUD DATE 6-14-65

2570 GR DRLG COMP _____

FR by DATA 6-14-65

COMP by " 8-26-65

LIBERAL ELECTRIC LOG TOPS

2579 KB

Winfield 2610 (+31)

Heebner 4212 (-1633)

Toronto 4236 (-1657)

Lansing 4356 (-1777)

Marmaton 5056 (-2477)

Morrow 5610 (-3031)

Lime 5726 (-3147)

"S-3" 5752 (-3173)

Chester 5764 (-3185); ϕ 4,250 MCF + 25 BOPD

Sand 6046 (-3467) 6/14

Ste. Gen 6096 (-3517)

TD 6198