

DST #6 (Ste Gen) 5848-5905, op 1 hr, GTS/45 min, rec 75' OCM +
400' oil + 200' MCO + 150' OCM, IBHP 1680/30, FP 110-240,
FBHP 1605/30:

7" @ 5905/360 sx. CO 5895, Sj log, Cem Bond log, 1/4295-96,
1/4316-17, SW/100 sx, 4/4296-97, 4/4310-11, 4/4314-15, SQ/150 sx,
16/5850-54, 80/5864-84 (Ste Gen) Tbg w/pkr @ 5830,
4/4305½-06½ (Tor) tbg to 4286, A/250 M, 5850-84, A/250,
4305½-06½, swb & flo 20 BOPH/NW/5 hrs, flo 30 BOPH/NW/12 hrs,
flo 7 BOPH ¼"ck, FTP 225, P 102 BOPD/NW, Miss 5850-84, G. (Miss)
oil 37.5°.

State Pot: (8 hr pump rate) Cal P 355 BOPD, NW, Tor 4305½-06½,
G. 42.5°.

LOG TOPS

2715 KB

Winfield 2732 (+17)
Council Grove 2972 (-257)
Heebner 4280 (-1565)
Toronto 4298 (-1583) P 355 BOPD
Lansing 4419 (-1704) mud
Marmaton 5082 (-2367)
Morrow 5586 (-2871)
Chester 5654 (-2939)
Ste. Gen 5715 (-3000)
St. Louis 5810 (-3095) Flo 102 BOPD
TD 5905