


9-118W MAP NO. 84 SEC. 27-34S-31W
 STATE Kansas COUNTY Seward LOC C SW NE
 OPER. Anadarko Production Co. - P.O. Box 351, Liberal FT/FR _____ LINE _____
 WELL #1 FARM York "A" KS Kansas FT/FR _____ LINE _____
 WC _____ ELEV. 2538 GR. 2548 DF 2551 KB _____
 CONT. Moran Bros. Drlg. GEOL. Cecil Little
 CO. INT. 6350' Miss Test
 F.R. 8-5-64 SPUD 8-6-64 COMP. 9-8-64
 TD. 6312 FM. St. Louis PBD. _____



COMP. RECORD

D & A

WC-1-3/4 mi SW of Kneeland (1 well) LKc O & Miss
Gas Pool 8-5/8" @ 2450' W/DV tool @626 w/350 SX.

Data Inc.

(GR Log Tops:)

Kri	2498	+ 40	Mrw sd	5670	-3132
Win	2590	+ 52	B/Mrw sd	5677	-3139
Tor	2260	-1722	Mrw sd	5740	-3202
Lans	4381	-1843	B/Mrw sd	5749	-3211
Marm	5078	-2540	Miss	5758	-3220
Chero	5234	-2696	Ste Gen	6053	-3515
Mrw	5616	-3078	St L	6137	-3599
			LTD	NA	
			RTD	6312	-3774

- DST #1 (Wab) 3405-23, Op 40", R 10' M, ISIP 756#/20", IFP 26#, FFP 40#, FSIP 701#/30"
- DST #2 (Wab) 3533-65, Op 70", R 1260' GCSW, ISIP 864#/30", IFP 232#, FFP 506#, FSIP 855#/30"
- DST #3 (Lans) 4747-70, Op 70", R 678' VSGCMSW, ISIP 1543#/30", IFP 120#, FFP 289#, FSIP 1431#/30"
- DST #4 (Chero) 5408-65, Op 37", R 20' M, NW, ISIP 66#/30", IFP 40#, FFP 40#, FSIP 55#/30"
- DST #5 (Mrw) 5663-5748, plg tool, R 30' M, ISIP 85#/30", IFP 85#, FFP 85#, FSIP 638#/30"
- DST #6 (Chest) 5754-5850, Op 70", R 20' M, ISIP 120#/30", IFP 44#, FFP 44#, FSIP 131#/30"
- WLT #1 (L Mrw) 5742½-45, Op 60", R 5 cc of gas, ISIP less than explosion/30', SP less than 50#, FSIP less 50#/20"
- WLT #2 (Lans) 4711-13½, Op 70", R 45, 420 cc wtr (10% SW), ISIP 1710#/10", SP 1700#/70", RTD 6312, SJ Log, D & A 8-31-64

COMPLETED

LIBERAL ELECTRIC LOG TOPS

2538 GL

Winfield 2586 (-48)

Heebner 4232 (-1694)

Toronto 4260 (-1722)

Lansing 4384 (-1846) WLT/wtr (10% XW)

Marmaton 5078 (-2540)

Morrow 5616 (-3078)

"S-1" Sand 5670 (-3132) 2/6/DST 30' Mud

"S-3" Sand 5728 (-3190) 5/16; WLT 5 cc gas

Chester 5748 (-3210) Tst mud

Ste. Gen 6070 (-3532)

St. Louis (Opr) 6138 (-3600)

TD 6312