


***** OFFSET

State KS Field W.C.
 Company TEXAS (50%) County SEWARD
 Farm G. M. GRUBER No. 1
 Sec. 12 Twp. 34 Range 31

Spot NE

Contractor NOBLE

Remarks GOOD MISS PAN AM DNM
GILCREASE (50%)



Comm. 12-12-57 Comp. 12-12-58
 Elev. DF 2713 GL 2705 KB 2715 TD 6029 PB 5820
 Pay MOR 5792-5808 53

I.P. ST GAS WELL Press. SITP 840
9.24 MCF
 Casing Record: 13 3/8 597/600 7"
 20" 103/4 5 1/2" 6029/250
 16" 85/8 2690/300

LOC.	Sample	Log
<u>DEC 18 SPUD</u> <u>\$2315</u>	<u>Heeb 4368</u>	<u>Heeb 4352</u>
<u>JAN 1 8 1/2 DST (CHASE)</u>	<u>LAN 4456</u>	<u>TOR 1677 4392</u>
<u>2827-43 op 35"</u>	<u>MARM 5210</u>	<u>LAN 4516</u>
<u>rec 40' M FP 0-0</u>	<u>CHER 5376</u>	<u>MARM 5192</u>
<u>BHP 600/30"</u>	<u>ATOKA 5603</u>	<u>CHER 5386</u>
<u>DST 4515-54 op 1 hr.</u>	<u>MOR 5750</u>	<u>ATOKA 5560</u>
<u>rec 35' M FP 0-0</u>	<u>" sd 5792</u>	<u>MOR 5713</u>
<u>BHP 1200/45" \$4900</u>		<u>CHESTER 5872</u>
<u>JAN 8 DST 5495-5531</u>		<u>ST GER 6014</u>
<u>op 1 hr. rec 810' G</u>		
<u>in pipe + 70' HGCM</u>		
<u>FP 37-57 BHP 581/45"</u>		
<u>DST 5680-5722</u>		
<u>op 2 hr. rec. 3382</u>		
<u>G in pipe + 218'</u>		
<u>HGCOil grew. 34"</u>		
<u>FP 75-90 BHP 550/60"</u>		
<u>\$5750</u>		

JAN 15 DST 5773-5803 op 2 hr. GTS 30"
53 TSTM rec. 75' HGCM IBHP 1785/45
FP 20-75 FBHP 1630/60"
DST 5811-35 op 1 hr. rec 30' G in
ch Drill pipe + rec 75' HGCM IBHP 350/30
FP 47 FBHP 99/45"

RTD 6029 ran log ~~5 1/2~~ WOC

JAN 22 MIST CO 6025 pf 28/6013-20

TST A/1000 swabbing @ 5820

JAN 29 Swab load N.S. apt 64/5792-

5808 N.S. ^{AP 50} FR/9000 sd/5000

swabbing on load flag 340 MCF
+ load & diminished rec. load

FR/12,000 sd/12,000 swab

g 539 MCF + load TST

FEB 5 g 240 MCF SI SITP 840

\$ SI GAS Well non-commercial

FEB 12

AMARILLO TOPS

2715 KB

Heebner 4374 (-1659)

Toro 4394 - 1679

Lansing 4516 (-1801)

Atoka 5520 (-2805) T

Morrow 5713 (-2998) T 115', 30' Tss

"S-2" 5731 (-3016) T 12', por 0', NT

"S-3" 5792 (-3077) T 18', por 10', G 240 MCF

Miss 5828 (-3113)

TD 6029 (-3314)