

A-8-14

OWWO

MAP NO.

ELEV. 2602 DF

STATE Kansas COUNTY Seward SEC. 14Twp 34S Rge 31WOPERATOR Panhandle Development Inc.

99' E of loc. C NE SE

WELL NO. 1 FARM NAME Keating

FT. FROM _____ LINE


TOL Kneeland

FT. FROM _____ LINE

FR. 2-3-61SPUD 1-27-61COMP. 7-28-61

CONT./GEOL.

NAME PRODUCING INTERVAL	COMPLETION RECORD		TREATMENT RECORD
	FROM - TO	PERF. W/HOLES	
a			
b			
c			
d			



I. P. OIL/DIST.	WTR.	GAS	M.C.F.P.D.	CHK.	HRS.
b	"	"	"	"	"
c	"	"	"	"	"
d					

Temporarily Abandoned D & A ()

SIP# _____ FI TP # _____

FI CP# _____ SIBHP _____

GOR. _____ GR. _____

PBDT _____ TD 6151

SIZE

DEPTH

CASING - CEMENT RECORD

SIZE

DEPTH

W/SAX.

13-3/8"638550OPERATOR Panhandle Devel. Inc. WELL NO. #1 Keating

ELEV. 2602 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Herrington	2428	
			Krider	2536	W 2630
			Heebner	4204	-31
			Kansas City	4384	
			Marmaton	5057	
			Atoka	5357	
			Morrow	5590	5600-3001
			Chester	5719	53-5702-3103
			Ste Genevieve	5862	317 M
			St Louis	6046	ch 5728-3129
			OTD	6149	56 5858-3209

Old Info: OWWO. Was D & A 1-21-53.

New Info: Re-entered 1-27-61. CO 6149 OTD. E-log. TD 6151.

5-1/2" @ 6150 w/250 sx. DV tool @ 4485 w/200 sx. RUST. CO 6060.

P/32/6048-56 (St L), Swb/NS, 1000 Ac, Rc ld. Swb ld/SSO&G, 3000

Ac, Rc ld, Swb 15 BSW / 1 1/2 BOPH/NT. PB to 6040.

P/4/6024-25 (Ste Gene), 4/6000-01 (Ste Gene). 16/5983-85 (Ste

Gen), 4/5958-59 (Ste Gene). 4/5907-08 (Ste Gen), NS Nat, 500

Ac, Rc ld/NS. PB to 5740.

Oh → P 24/5722-28 (Chest), NS, 1500 Ac, rec ld, g 250 MCF, 15,000 Ac, rec ld, g 1,250 MCF, set BP @ 5714.

no → P 20/5694-99, g 850 MCF, 1500 Ac, rec ld, g 1,000 MCF, 15,000 Ac, frac 10,000 Ac X 20,000 Sd, rec ld, g 2,000 MCF, set BP @ 4910.

P 16/4901-05, sq w/cem. CO to 4910.

Lo Lsg → P 20/4902-07, flod XW (no est). SQ 4902-07 w/150 sx. CO 4470. P 20/4458-63, swb 27 BXW + 3 BXWPH, SQ/4458-63/75 sx. CO 4250.

Lsg → P 16/4242-46, 500 MA, swb ld w/SSO. SQ 4242-46/75 sx. CO 3330.

Top Lsg "Toronto" → P 4/3323-24, 500 MA, rec ld/NS, SQ 3323-24 w/75 sx. CO 5714. 4 hr BD g 1,500 MCF, from Morrow 5694-99.

Had Communication between zones.

Temporarily Abandoned

Complete 7/29/61.