

JUL 25 1970

WELL LOG

24-34-32W
C SW NE
24-34-32W

Company Leben Drilling, Inc.

Sec. 24 T. 34S R. 32W

Contractor Leben Drilling, Inc.

Loc. C SW NE

Farm Beers #1

County Seward


Total Depth 6454' RTD

Casing 8 5/8" N.C. 24# set @ 1490' w/650
sxs. Pox. 6% Gel, 2% C.C. & 235 sxs.
Production Common 2% C.C.
Producer

Commenced 4-17-70


Completed 5-9-70

4PT / 3360 MCF GPD
LKC



Figures Indicate Bottom of Formations

330	Surface
1190	Sand & Red Bed
1486	Red Bed
1490	Anhydrite
1545	Anhydrite & Red Bed
1850	Red Bed, Shells & Gyp
2370	Shale & Shells
3850	Shale & Lime
4065	Shale & Ck. Lime
4344	Shale & Lime
5539	Lime
6002	Lime & Shale
6005	Lime
6221	Lime & Shale
6454	Lime
<u>6454</u>	<u>RTD</u>



Heubner 4385
LKC 4543
KC 4835

State of Kansas

SS

City of Barton