

WELL COMPLETION REPORT AND
 DRILLER'S LOG

API No. 15 — 175 — 20,377
 County Number

Loc. C SE/4
 County Seward

Operator Gulf Oil Corporation

Address P. O. Box 12716, Okla. City, OK 73157


Well No. 2-1 Lease Name Rice Davies

Footage Location 1320 feet from GMD (S) line 1320 feet from (E) WBO line

Principal Contractor Rains & Williamson Oil Co., Inc. Geologist -

Spud Date 10-26-78 Date Completed 1-26-79 Total Depth 6300' P.B.T.D. 6253'

Directional Deviation - Oil and/or Gas Purchaser Anadarko Production Co.



Locate well correctly
 Elev.: Gr. 2584'

DF 2591' KB 2593'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12-1/4"	8-5/8"	24#	1545'	CL "H"	650	2% CaCl 16% Gel
	7-7/8"	5-1/2"	15.5#	6300'	50-50 Poz	225	Displaced w/500 gal Acetic Acid &
							2% KCl wtr.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
-	-	-	Total of 11 holes	.33" Omega Gun	5738-5748'
TUBING RECORD			Total of 9 holes	.33" Omega Gun	5761-5769'
Size	Setting depth	Packer set at			
2-3/8"	5764.20'	-			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1500 gal 10% HCL acid	5738-5748'
Frac w/25,000 gal Versagel 2400 & 30,000# 20-40 sand.	5761-5769'

INITIAL PRODUCTION

Date of first production 1-5-78	Producing method (flowing, pumping, gas lift, etc.) Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil 2 bbls. Gas AOF= 2.5 MMCFPD MCF Water 11 bbls. Gas-oil ratio 5000 CFPB
Disposition of gas (vented, used on lease or sold) Will be sold but vented during testing	Producing interval(s) 5738-48' & 5761-69'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

erator

Gulf Oil Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Gas

Well No.

2-1

Lease Name

Rice Davies

1 T34S R 32W W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Red Bed & Sand	0	981'		
Shale & Lime	981	2486		
Lime	2486	3086		
Lime & Shale	3086	3750		
Shale	3750	4410		
Shale & Lime	4410	6140		
Shale	6140	6300'	TD	
	+			
		6256	PBTD	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

[Signature]
Signature

Senior Clerk
Title

August 6, 1979
Date