

7-34-32W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- ANADARKO PRODUCTION CO.  
Farm- Condit "A" No. 1

SEC. 7 T. 34 R. 32W  
C NW SE

Total Depth. 6420'  
Comm. 10-26-62 Comp. 11-14-62  
Shot or Treated.  
Contractor. Midwestern Drillers, Inc.  
Issued. 2-16-63

County Seward  
KANSAS



Elevation. 2824.12' GL

CASING:  
8 5/8" 1627' cem w/900 sx.

Production. DRY

Figures Indicate Bottom of Formations.

surface sand	280
surface sand & shale	700
red bed & gypsum	1605
anhydrite	1630
anhydrite & red bed	2570
anhydrite & shale	2715
shale & lime	4543
lime	4600
lime & shale	5060
lime	5180
lime & shale	5279
lime	5520
lime & shale	6015
lime	6030
lime & shale	6290
lime	6360
lime & shale	6415
lime	6420 RTD
Total Depth	

TOPS: LOG	
Krider	2702
Winfield	2797
Council Grove	3064
Toronto	4395
Lansing	4541
Morrow	5781
Lower Morrow Sand	5953 - 5983
Chester	6003
Chester Sand	6294 - 6302
Chester Sand	6314 - 6323
Ste. Genevieve	6326