

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


13-34-32W

Company- ANADARKO PRODUCTION CO.
Farm- Davies "B" No. 1

SEC. 13 T. 34 R. 32W
C SE NW

Total Depth. 6612'
Comm. 9-30-61 Comp. 11-7-61
Shot or Treated.
Contractor. Herndon Drlg.
Issued. 1-27-62

County Seward
KANSAS



Elevation. 2751' KB

Production. Dry

CASING:

8 5/8" 2625' cem w/1150 sx.
4 1/2" 4704' cem w/250 sx.

Figures indicate Bottom of Formations.

surface hole	2616
sand	2770
sand & lime	2895
lime & shale	3155
lime & chalk	3300
lime & chert	3330
lime & chalk	3530
lime	3585
lime & chalk	3720
lime	3870
lime & shale	4080
shale	4260
lime & shale	4355
lime	4455
lime & shale	4555
lime	5400
lime & chert	5455
lime & shale	5499
lime	5724
lime & shale	6336
lime	6488
lime & shale	6532
lime	6588
lime & chert	6591
lime	6612

Total Depth

TOPS: SCOUT

Herrington	2664
Upper Krider	2691
Winfield	2778
Council Grove	3060
Toronto	4411
Lansing	4540
Marmaton	5247
Cherokee	5397
Morrow	5791
Lower Morrow	5947
Chester	5971
St. Genevieve	6266
St. Louis	6371

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
Lansing	4551	4553	8	1750	7½%
Shawnee	4145	4149	16	500	