

KANSAS

P2

IMPORTANT
Kans. Geo. Survey request
samples on this well.

WELL COMPLETION REPORT AND
DRILLER'S LOG

S. 13 T. 34 R. 32 W

Loc. NW NE

County Seward

API No. 15 — 175 County — 20 509 Number WICHITA BRANCH

Operator
Monexco

Address
101 Park Ave, Suite 1300 Okla City 73102


Well No. #1-13 Lease Name Davies

Footage Location
660 feet from (N) ● line 1980 feet from (E) ● line of 1/4 Sec.

Principal Contractor Service Drilling Company Geologist Ernie Otto

Spud Date 7/3/81 Date Completed 7/23/81 Total Depth 6450 P.B.T.D. P & A

Directional Deviation _____ Oil and/or Gas Purchaser _____



Elev.: Gr. 2726'

DF 2732' KB 2735'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	23#	1520'	Lite Class H	600 150	3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
60 sacks common cement @ 3000' 50 sacks common cement @ 1450'	
25 sacks common cement @ 700' 10 sacks common cement @ 0 to 40'	
5 sacks in the rat hole.	

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 Na. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator _____ DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1-13 Lease Name Davies Dry hole

S 13 T 34S R 32 W Seward County, Kansas


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Herrington Lime	2630	2748		
Windfield (Sand & Shale)	2748	2998		
Council Grove (Shale)	2998	3714		
Topeka (Limestone & Shale)	3714	4358		
Heebner Shale	4358	4382		
Toronto (Limestone)	4382	4529		
Lansing (Limestone)	4529	5008		
Marmaton (Limestone)	5008	5378		
Cherokee (Sand & Shale)	5378	5776		
Morrow (Sand & Shale)	5776	5946		
Chester (Limestone)	5946	6254		
St. Genevieve	6254	6370		
St. Louis	6370	6464 TD		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature
	Agent Title
	August 6, 1981 Date