

18-34-32W

DRILLER'S LOG

WELL NAME: Dodd "B" No. 1 ; COMPANY OPERATING: Anadarko Production Company
 ADDRESS of COMPANY: Box 351, Liberal, Kansas
 WELL LOCATION: C 1/4 SW 1/4 SW 1/4,
660 ft. North of South line,
660 ft. East of West line; Sec. 18, Twp. 34S, Rge. 32W, Seward County, Kansas
 DRILLING STARTED July 18, 1965; DRILLING COMPLETED August 3, 1965
 WELL COMPLETED August 7, 1965; WELL CONNECTED _____, 19____
 ELEVATION: 2801.14 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Oil

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
<u>Chester</u>	<u>6262</u>	<u>80</u>	<u>30</u>	<u>2,000</u>	<u>10% NE Acid</u>

KANSAS GEOLOGICAL SURVEY
 WELLS DIVISION

DEC 21 1987

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
<u>8-5/8"</u>	<u>1588</u>	<u>700</u>	<u>None</u>
<u>4-1/2"</u>	<u>6381</u>	<u>175</u>	<u>None</u>
<u>2-3/8"</u>	<u>6265</u>		<u>None</u>

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
<u>Red Bed & Surface Clay</u>	<u>0</u>	<u>1126</u>			
<u>Anhydrite & Red Bed</u>	<u>1126</u>	<u>1588</u>			
<u>Red Bed, Anhydrite & Gyp Shale</u>	<u>1588</u>	<u>2368</u>			
<u>Shale & Lime</u>	<u>2368</u>	<u>3265</u>			
<u>Lime & Chalk</u>	<u>3265</u>	<u>4913</u>			
<u>Lime</u>	<u>4913</u>	<u>5745</u>			
<u>Lime & Shale</u>	<u>5745</u>	<u>6251</u>			
<u>Shale & Sand</u>	<u>6251</u>	<u>6293</u>			
<u>Shale & Lime</u>	<u>6293</u>	<u>6380</u>			
<u>Lime</u>	<u>6380</u>	<u>6386</u>			
<u>Total Depth</u>		<u>6386</u>			

RESULTS of INITIAL PRODUCTION TEST: 157.7 barrels of oil in 16 hours.