

31-34-32W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WHITESTONE PETROLEUM CORP.
Farm- L. G. Blackmer No. 1

SEC. 31 T. 34 R. 32W
C NE SW

Total Depth. 6710'
Comm. 12-10-62 Comp. 1-8-63
Shot or Treated.
Contractor. Roberts Drlg.
Issued. 6-19-65

County Seward
KANSAS



Elevation. 2847' RB

Production. 5,800,000 CFG

8 5/8" 2290.92 cem w/ 295 x
4 1/2" 6266.26' cem w/ 275 sx

Figures Indicate Bottom of Formations.

surface clay	175
sand	550
red bed	825
sand, lime	875
sand & shale	1200
shale & red bed	1448
Gyp & Anhydrite strks	1474
red bed & anhydrite strks	1630
anhydrite & lime strks	1785
shale & lime strks	1895
shale & lime	2270
anhydrite	2290
shale & anhydrite	2340
lime & shale	2750
lime	3095
lime & chalk	3740
lime	3851
shale & lime	4485
lime	4556
cherty lime	4602
lime	4790
lime & shale	4920
lime & shale strks	5068
lime	5565
lime & shale	5980
shale, lime & sand	6075
shale & lime	6153
lime	6260
lime & shale	6384
lime	6634
cherty lime	6654
lime & shale	6688
lime	6710
Total Depth	

TOPS:SCOUT	
Toronto	4387
Lansing	4534
Morrow	5826
Morrow sand	6022-43
Mississippi	6070