

COPY

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 175 — 20,460
 County Number

S. 34 T. 34S R. 32 R W
 Loc. 200' SW of NW NE SW

County Seward

Operator
General Oil Distributors, Inc.

Address
P.O. Drawer 1869, Liberal, KS 67901


Well No. 1 Lease Name Breen-Renfro

Footage Location
1980+ feet from (N) (S) line 1320+ feet from (E) (W) line

Principal Contractor DaMac Drilling, Inc. Geologist

Spud Date 5-1-80 Date Completed 5-17-80 Total Depth 6270 P.B.T.D. 6000

Directional Deviation Oil and/or Gas Purchaser



Elev.: Gr. 2779'

DF 2787' KB 2788'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	1488	light Class H	550	2% cc
Production	7 7/8"	4 1/2"	10.5#	6076	Class H	200	3% cc
					50/50 poz	50	8% gel, 12 1/2#
						150	Gilsonite, 10% salt
							18% salt, 12 1/2#
							Gilsonite, .7% Hala
							9, .75% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	.38 DP	5917-21
			4	Tornado jets	5917-21

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
750 gal 15% HCS (formation would not break down)	5917-21

RECEIVED
 STATE CORPORATION COMMISSION

INITIAL PRODUCTION

JUL 21 1980

Date of first production Producing method (flowing, pumping, gas lift, etc.)
 CONSERVATION DIVISION
 Wichita, Kansas

RATE OF PRODUCTION PER 24 HOURS Oil Gas Water Gas-oil ratio
 bbls. MCF bbls. CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

General Oil Distributors, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Dry Hole

Well No. 1

Lease Name Breen-Renfro

S 34 T 34SR 32 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Sand	0	55	Toronto	4452'-1664'
Clay	55	660	Lansing	4580'-1792'
Sand, Shale	660	1490		
Red Bed	1490	2271		
Shale, Lime	2271	2975		
Dolomite	2975	3435		
Lime, Shale	3435	6270		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Neil E. Lowery
Signature

Agent, General Oil Distributors, Inc.
Title

July 17, 1980
Date